

APPLICATION REQUESTS

City of Caldwell

Community Development Department - Planning & Zoning Division

MASTER LAND USE APPLICATION

This Master Land Use Application and specific land use checklists must be completed, with all required supplemental documents provided and fees paid for an application to be considered complete and accepted. Once accepted, all applications go through pre-screening prior to being routed for the initial review.

Failure to submit all requested items (in legible form) may delay the processing of your application. Additional information may be required during pre-screening or after the review of your proposal.

Please note that any land use action below marked with an asterisk (*) will require public hearing. Land use actions below marked with two asterisks (**) may require public hearing depending on the scope of project.

Note: Please check all specific land uses actions bel	ow that you are applying for	
\square Accessory Dwelling Unit (ADU)	☐ *Manufactured Home Community	☐ Subdivision Plats
\square Director Determination	☐ Outdoor Dining Permit	☐ *Preliminary Plat
\square Administrative Development Review	☐ Parcel Consolidation	☐ Final Plat
☐ *Annexation w/ Zoning	\square Planned Unit Development (PUD)	*Short Plat (Regular)
☐ Business Permit (Business License)	□ *New	☐ *Short Plat (Condo)
☐ *Certificate of Appropriateness	☐ **Modification	☐ **Plat Modification ³
☐ *Comprehensive Plan Amendment	☐ Public Art / Murals	□ *Replat
☐ *Deannexation	☐ *Rezone (Zoning Map Amendment)	☐ Time Extension
☐ **Design Review	☐ Signs¹	☐ Renewal
☐ Development Agreement	☐ Site Plan / Landscape Plan Review²	☐ Temporary Use Permit
□ *New	☐ Special Use Permit (SUP)	□ New □ Renewal
**Modification	□ *New	☐ Mobile Food Unit
☐ *Termination	☐ **Modification	☐ Temporary Use Facility
\square Home Occupation Permit	☐ Time Extension	☐ Transient Merchant Facility
□ New		☐ Traffic Impact Study Review
☐ Renewal		☐ Vacation
☐ Lot Line Adjustment		□ *Variance
☐ Lot Split		☐ *Zoning Text Amendment
☐ Administrative		
☐ Simple		

¹ Freestanding, post/pole, or monument signs less than 6' in height. All other signs must be submitted through the building department.

² Used when not associated with other land use applications or construction drawing submissions.

³ Re-plats are not considered plat modifications.

City of Caldwell

Community Development Department – Planning & Zoning Division

MASTER LAND USE APPLICATION

PROJECT and SITE/PROPERTY INFORMATION			
Project or Business Name:			
Site Address (s):	Suite #:		
Parcel #(s):			
Total Acres:			
General Location of Site:			
Current Zoning of Parcel(s):	□ RS-1 □ RS-2 □ R-1 □ R-2 □ R-3 □ C-1 □ C-2 □ C-3 □ C-4 □ C-C		
(check all that apply)	\square M-1 \square M-2 \square I-P \square A-D \square C-D \square H-D \square P-D \square T-N \square H-C		
	☐ County Zone:		
	□ Not Applicable		
Overlay Districts:	□ Not Applicable□ APO-1 □ APO-2 □ HD-1 □ City Center Indian Creek Corridor		
(if applicable)	☐ City Center Local Historic Area ☐ None ☐ Not Applicable		
Is Parcel(s) in Floodplain:	☐ Yes ☐ No		
Description of Proposed Project /	Request:		

City of Caldwell

Community Development Department – Planning & Zoning Division

MASTER LAND USE APPLICATION

APPLICANT INFORMATION:
Name:
Company Name (if applicable):
☐ Property Owner ☐ Authorized Agent ☐ Purchaser ☐ Petitioner (Vacations only)
Mailing Address:
Phone:
Email:
PROPERTY OWNERS' INFORMATION (If an LLC, please provide documentation of being an authorized signer)
☐ Not Applicable
Name:
Mailing Address:
Phone:
Email:
DESIGNATED CONTACT PERSON (Who will receive and disseminate all correspondence from the city)
Same as:
☐ Applicant ☐ Property Owner ☐ Other
Name:
Company Name (if applicable):
Mailing Address:
Phone:
Email:

CONTRACTOR / DEVELOPER INFORMATION
☐ Not Applicable
Name:
Company Name (if applicable):
Mailing Address:
Phone:
Email:
ARCHITECT INFORMATION
☐ Not Applicable
Name:
Company Name (if applicable):
Mailing Address:
Phone:
Email:
ENGINEER / SURVEYOR INFORMATION
□ Not Applicable
Name:
Company Name (if applicable):
Mailing Address:
Phone:
Email:



City of Caldwell

Community Development Department – Planning & Zoning Division

MASTER LAND USE APPLICATION

LANDSCAPE ARCHITECT INFORMATION		
☐ Not Applicable		
Name:		
Company Name (if applicable):		
Mailing Address:		
Phone:		
Email:		
ACKNOWLEDGEMENTS		
☐ By signing this application, I authorize employees/agents of the City to enter onto the property that is		
the subject of this application during regular business hours. The sole purpose of entry is to make an examination of the property that is necessary to process this application.		
I certify that I am the owner of this property, the owner's authorized agent, or the petitioner (if for a vacation). If acting as an authorized agent, I further certify that I have full power and authority to file this application and to perform, on behalf of the owner, all acts required to enable the jurisdiction to process and review such an application. I will comply with all provisions of the law and ordinance governing this type of application.		
\Box I certify that the information furnished by me as part of this application is true and correct to the best of my knowledge.		
I am the: \square Property Owner \square Authorized Agent \square Petitioner (Vacations Only)		
Applicant Signature:		
Printed Name:		

Online Application Submittal Instructions

The City of Caldwell Planning and Zoning Department utilizes an online application portal for submission of all applications, documents, plans, and payment of fees.

Step 1:

- Log in or create an account in Citizenserve (Citizenserve Users Guide)
- Select your permit and/or application type and enter in all required information.

Step 2

• Pay fees online via Citizenserve. You will receive an email from Citizenserve directing you to make a payment once staff have reviewed your application.

Drawing Submittal Instructions:

- 1. All plan sheets must be uploaded in PDF format only (no CAD, JPEG, TIFF, PNG, etc.)
- 2. All plan sheets must be to scale.
- 3. All plan sheets must be uploaded to Citizenserve.
- 1. All applications, checklists, calculations, reports, drawings, plans, and other supporting documents must be uploaded as single-sided pdf's and must be legible and in a high-definition format.



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

SUBDIVISION PRELIMINARY PLAT CHECKLIST

The following items shall be included in any application submittal. Additional information may be required, as indicated in your roundtable (pre-app) meeting or upon official review of the plans. Please check the box for each item listed below to confirm submission of the item listed.

SECTION I

SUBMITTAL DOCUM	IENTS & RELATED PLANS	Applicant	Staff
Master Land Use Application	Copy of completed, signed and dated application		
Application Checklist	Copy of completed, signed and dated checklist		
Property Owner Acknowledgement	If the signatory of the application is not the owner of the property, a notarized statement (property owner acknowledgement) must be signed by the legal owner of record and submitted with the application		
Proof of Property Ownership	Recorded Warranty Deed for the subject property showing proof of ownership, or evidence of property interest to subject property		
Legal Description of Property	Attach a legal description of the property including metes and bounds to the centerline of all adjacent rights of ways. All legal descriptions shall be certified by a land surveyor registered to the State of Idaho.		
Neighborhood Meeting Information	 The verification shall include: A copy of the letter mailed by the applicant (Min. 15 days prior to meeting) A copy of the 500' mailing list indicating all notified owners, residents and associations A copy of the sign-up sheet from the meeting, with your signature Note: Neighborhood meetings must have been held within four (4) months of application submission. 		
Photographs	Photographs of existing site conditions		
Project Narrative	Narrative fully describing the application request(s), the purpose of the development, existing site conditions, and what is being proposed.		
Concept Building Elevations	Colored concept elevations of all four (4) sides of buildings, indicating building heights, colors, materials, windows, doors, and architectural features.		
Site Plan (Scaled)	Site plan, drawn to scale, showing location of all property lines, existing and proposed buildings, utilities, setbacks, easements, and streets with street names.		
Preliminary Plat	High resolution preliminary plat, to scale. See requirements for plan content in Section II below		
Landscape Plan	High resolution landscape plan, to scale. See requirements for landscape plan contents in Section III below		



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

SECTION II

PRELIMINARY PLAT	CONTENT	Applicant	Staff
Plans to Scale	All mapped data for the same plat shall be drawn at a scale suitable to ensure the clarity of all lines, bearings and dimensions, said scale typically being one hundred feet to an inch (100' = 1"). Whenever practical, scales shall be adjusted to produce an overall drawing measuring eighteen inches by twenty- four inches (18" x 24"), but not exceeding forty-two inches by sixty inches (42" x 60").		
Subdivision Name and Location	 The proposed subdivision name and location shall be provided on the plat and shall meet the following: Said name shall be approved by the City Mapping Department and shall not being a duplicate name of any other recorded subdivision within Canyon County or any of the cities in Canyon County; Location of subdivision by section, township and range; reference by dimension and bearing to a combination of two (2) section corners, quarter section corners, or recorded monuments. (Ord. 3374, 12-6-2021) 		
Contact Information	Name, address and phone number of property owner(s), subdivider, engineer, planner, and surveyor who prepared the plat, and any other professional persons involved in the subdivision.		
Scale, North Arrow, and Plan Preparation Date	Scale, north arrow and date of preparation including dates of any subsequent revisions.		
Vicinity Map (Scaled)	Vicinity map drawn to a maximum scale of one inch equals five hundred feet (1" = 500'), clearly showing the proposed subdivision or planned unit development configuration in relationship to, as well as, identifying and showing lot lines and street connections of all adjacent subdivisions, all arterial streets, all collector streets and bodies of water.		
Topography	Topography based on NAVD 88 datum shown on the same map as the proposed subdivision layout. Contour lines shown at five foot (5') intervals where land slope is greater than ten percent (10%) and at two foot (2') intervals where land slope is ten percent (10%) or less, referenced to an established bench mark, including location and elevation.		
Existing Water	Location of existing water wells and type, streams, canals, irrigation laterals, drainage facilities, private ditches, washes, lakes and other water features; direction of flow; regulatory floodplain and floodway boundaries if any; and location and extent of known areas subject to inundation if any.		
Streets and other Important Features	Location, widths and names of all existing streets and location, arrows indicating direction of slopes, type of surface and existence of any curb, gutter and/or sidewalks. Other important features such as railroads, utility rights of way and easements of public record, public areas, permanent structures to remain including water wells, and municipal corporation lines within or adjacent to the tract.		
Recorded Subdivisions with Common Boundaries	Name, book, page number and lot line layout of any recorded adjacent subdivision having common boundary with the tract.		
Table Schedule (see attached example)	Table Schedule of: Existing zoning classification of the tract with any requested zoning changes. Total acreage of the entire subdivision Total number of buildable lots by land use type. Total number of common lots. Total gross acreage Average buildable lot size Dwelling units per gross acre.		



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

PRELIMINARY PLAT	CONTENT cont.	Applicant	Staff
Subdivision Boundary	The subdivision boundary with dimensions and bearings shall be based on an actual recorded field survey, performed within six (6) months of the preliminary plat application, and shall include the professional land surveyor stamp. Boundary problems shall be resolved prior to preliminary plat submittal. Stamping of the preliminary plat by the professional land surveyor pertains only to the boundary survey and should be noted as such.		
Public dedications of rights of way or easements	Proposed location, width, dimensions and bearings, and use of all proposed easements within the subdivision. All existing easements with location, width, dimensions, bearings, use and instrument numbers. Designation of all land to be dedicated or reserved for public use with purpose indicated.		
Names, Addresses, and Tax Parcel Numbers	Names, addresses and tax parcel numbers for all property owners within three hundred feet (300') of the exterior boundary of the subdivision, displayed visually on the plat in the appropriate locations.		
Utilities	Storm drains and water supply mains, both proposed and existing, within and immediately adjacent to the subdivision. Approximate location of existing sanitary sewer facilities, manholes, lines, and any other sewer related facilities within and adjacent to the subdivision.		
Proposed Street Layout	Proposed street layout, including location, width and proposed names of streets, common driveways, alleys, major pathways, micro pathways and easements; pedestrian and vehicular connections to adjoining properties.		
Lot Dimensions	Typical lot dimensions to scale; dimensions of all corner lots and lots of curvilinear sections of streets; each lot and block numbered individually; each lot labeled with its individual lot acreage and square footage.		
Land Use and Zoning Classification (Each Area)	If plat includes land for which multi-family, commercial, industrial or mixed use is proposed, such areas shall be clearly designated together with existing zoning classification and status of zoning change, if any.		
Special Development Areas	Appropriate information that sufficiently details the proposed subdivision within any special development area, such as: Hillside Floodplain		
On and Off-Site Improvements	The proposed on and off site improvements including water supply systems, sanitary sewer systems and stormwater drainage.		
Access and Approaches	Width, spacing and location of all proposed approaches to the subdivision with type (example: full approach, right in/right out approach) of approach indicated.		
Proposed Utility Methods	 (A) Sewage Disposal: Such evidence relative to the design flows within the subdivision, and operation of the sanitary sewage facilities proposed. A statement as to the type of facilities proposed shall appear on the preliminary plat. (B) Water Supply: Such evidence relative to the design, operation, volume and quality of the water supply and facilities proposed. A statement as to the type of facilities proposed shall appear on the preliminary plat. (C) Stormwater Disposal: Such evidence relative to the design and operation of the stormwater disposal system. A statement as to the type of facilities proposed, and an indication of all areas to be used for treatment/disposal shall appear on the preliminary plat. All stormwater design shall comply with the city's most recent "Stormwater Management Manual" as adopted by council as of the date of preliminary plat application submittal. (D) Irrigation System: A statement describing the proposed irrigation system, consistent with section 10-07-12 of the Caldwell City Code, shall appear on the preliminary plat. 		



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

PRELIMINARY PLAT	CONTENT cont.	Applicant	Staff
Acknowledgement	Note acknowledging that, to the best of the preparer's knowledge, the preliminary plat meets all requirements of city code; or if said plat does not meet all requirements then the plat has been submitted as a planned unit development and any and all requested exceptions have been listed in detail as part of the planned unit development application or it is not a planned unit development but any exceptions as allowed in this chapter have been noted on the preliminary plat and specifically requested as a part of the application.		

SECTION III

LANDSCAPE PLAN C	CONTENT (CCC 10-07-03)	Applicant	Staff
Plan Preparation	Landscaping plans shall be prepared by a landscape architect, a landscape designer or a qualified nursery person; Landscape plans shall be stamped by a licensed landscape architect.		
Plan Size	Detailed plan at a scale no smaller than one inch equals fifty feet (1" = 50')		
Streets, Setbacks and	Show all streets, setbacks, and easements, Streets shall be identified by name.		
Easements	Dimension and label all right-of-way, setbacks, and easements		
Sight Visibility Triangles	Show and label all sign visibility triangles.		
Storm Water Facilities and Berms	Show all storm water facilities and berms. Indicate berm heights, slopes and proposed landscaping		
Off-Street Parking & Bicycle Parking	 A note listing the required number of parking spaces and bicycle parking spaces. A note listing the provided number of parking spaces and bicycle parking spaces. The provided number of parking spaces and bicycle parking spaces shall equal or exceed the required number of parking spaces and bicycle parking spaces. Circulation area required to serve the parking spaces with typical dimensions. 		
Existing Trees and/or Shrubs	Location of all existing trees and shrubs, and the approximate size and type of any existing trees and shrubs. Indicate by note which trees and/or shrubs will remain, if any.		
Existing and Proposed Structures	Location of all existing and proposed structures and a note of whether or not the existing structures will remain		
Pathways	Location, width, and type of pathways, along with identification of all required pathway materials and landscaping callouts: • Micro Pathways • Major Pathways • Public Pathways • Regional Pathways • Indian Creek Corridor Pathways (if applicable)		
Open Space Exhibit	 All open space clearly delineated using colored shading so it is readily identifiable. The open space exhibit shall contain a table identifying: The percentage and acreage of each individual areas of open space and if the open space is being calculated as qualified open space The total percentage and acreage of code required open space and qualifying open space in relationship to the gross area of the project The total percentage and acreage of proposed open space and qualifying open space in relationship to the gross area of the project 		
Public Amenities	Location, size, and types of new structures for recreational use (i.e., gazebos, water features, picnic areas, shuffleboard, etc)		



621 Cleveland Blvd., Caldwell, Idaho, 83605

Phone: (208) 455-3021 | Web: www.cityofcaldwell.org

LANDSCAPE PLAN CONTENT (CCC 10-07-03)		Applicant	Staff
School Bus Stops	Location of school bus stop areas within a common lot or common easement		
Public Transit Stops	Location of any public transit		
Street Landscape	Location and width of all street landscape buffers. Include the location of all sod,		
Buffers	trees, shrubs, plantings, and other materials proposed.		
Landscape Buffers	Location and width of all landscape buffers between different land uses. Include the		
Between Land Uses	location of all sod, trees, shrubs, plantings, and other materials proposed.		
Parking Lot	Location and size of all landscape islands within parking lots, Include the location of		
Landscaping	all landscaping materials proposed		
Trash Enclosures	Location of all trash enclosures, to include details about screening and landscaping		
Fencing	Location, height, color, and materials for all existing or proposed fencing		
Other Landscape	Provide location, size, type and description of all other landscape improvements such		
Amenities	as berms, decorative rock, boulders, etc.		
Landscape Schedule	Provide a table listing all of the locations, descriptions, types and numbers of		
	landscaping products to be installed.		

SECTION IV

GENERAL PROJECT INFORMATION					
	mmm				
Type of land uses within subdivision:	Residential only	Commercial only Ir	dustrial only		
	Mixed-use (mix of re	sidential and non-residentia	l uses)		
Has your development / subdivision name, street names, and lot and block numbers been approved by the City of Caldwell Mapping Division?	Yes No If yes, have you made a approved by Mapping?		s to the previously approved pre-plat		
Will the subdivision be phased?	Yes No.3				
	If yes, how many phases are proposed?				
Development timeline for full build out?	out?				
LAND USE AND ZONING INFORMAT	ΓΙΟΝ				
	Zoning Designation	Comp Plan Designation	Land Use		
Existing (Subject Property)					
Proposed (Subject Property)					
North of Site					
South of Site					
East of Site					
West of Site					



621 Cleveland Blvd., Caldwell, Idaho, 83605

PROJECT SPECIFIC IN	IFORM	ATION								
			Num	ber of Lo	ts	Acres		Net ac	Percent of "Net" Acres Net acreage is the total acreage minus any public streets and public rights of way	
Residential Lots									way	
Commercial Lots										
Industrial Lots										
Common Lots										
EXISTING AND PROPO	SED B	UILDII	NG DAT	A						
		# of # of EXISTING PROPOSED buildings buildings			SED	# of EXISTING dwelling units	# of PROPOSED dwelling units		Max. Building Height	Total GROSS square footage of buildings
Residential:										
Single-family (detached)										
	homes									
Two-family (c Three-family residential (
Four, five and six	family									
(fourplex, fiveplex, and s										
Multi-family (7 or > documents) in a single b	welling	elling								
Commercial						N/A	N/A			
Industrial						N/A	N/A			
Type of Commercial or Industrial Buildings:	Single-tenant building(s) Multi-tenant buildings									
DENSITY AND OPEN S	PACE	(Comp				<u>C 10-07-05)</u>				
Dwelling units per gross acre (Density):	Max. Allowed								Proposed	
% Required					% Proposed					
Total Open Space	% Kequired						% гтороѕеч			
Total "Qualifying" Open			%	Required					% Proposed	
Space Space				•					·	
Included	highlig	NOTE: Attach a separate Open Space Exhibit showing all areas of open space highlighted, all areas highlighted and labeled for qualifying open space, and table with breakdown, square footage, percentage and acreage of all open space vs. qualifying open space.								



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: www.cityofcaldwell.org

PARKING, LOADING AND PEDESTRIAN AMENITIES (CCC 10-02-05) Min. Required Description **Proposed** Electric vehicle parking spaces Off-street parking spaces Commercial loading spaces Industrial loading spaces Bicycle parking spaces: Describe any public transportation facilities that will be provided in accordance with (CCC 10-02-05 B) Public Amenities: Provide a description of the type of public amenities proposed: LANDSCAPING AND PATHWAYS (CCC Chapter 10, Article 7) Landscaping: (Please check all Street landscape buffers locations where landscaping will be Common areas Parking lot provided) Between different land uses Pathways **Around building exterior** Other_ Major Pathways Describe location, width, and landscaping: Micro Pathways Describe location, width, and landscaping Public Pathways Describe location, width, landscaping, and any proposed fencing: (per Bicycles and Pathways Master Plan)



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

STREET LANDSCAPE I	BUFFERS (C	CC 10-07-08)						
Location Min. (Enter Street Name) Width Required		Proposed Width	% of Sod Proposed	# of Trees Proposed	l Sp	n. Tree pacing n feet)	# of Shrubs Proposed	Min. Shrub Spacing (in feet)
BUFFERS BETWEEN L	AND USES (C	CC 10-07-10)						
Location (If not required, put N/A)	Min. Width Required	Proposed Width	% of Sod Proposed	# of Trees	d S	n. Tree pacing n feet)	# of Shrubs Proposed	Min. Shrub Spacing (in feet)
North Property Line								(III 100 J)
South Property Line								
East Property Line								
West Property Line								
PUBLIC SIDEWALKS		100						
Location (Street Name)		Min. Width Required	n Proposed Width			Type of	Sidewalk	
		•		Me	andering	/	Attached	Detached
					andering	<u>,</u>	Attached	Detached
					andering		Attached	Detached
				Me	andering	,	Attached	Detached
UTILITIES, INFRASTRU	CTURE, AND	PUBLIC SERV	ICES INFORMA	TION				
			vidual Domestic W		any?			
	Centralized Public Water System							
Domestic Water:	City Municipal Water System							
	N/A							
	Nearest Water Line Connection:							
			vidual Septic					
Sewer (Wastewater):	City Municipal Sewer							
Sewei (wasiewalei).	N/A							
		Nearest Sew	er Line Connection	on:				
			face					
	Irrigation Well							
	Pressurized							
Irrigation:			vity					
		N/A						
			ation Connection	:				
		Irrigation Dis	strict:					



621 Cleveland Blvd., Caldwell, Idaho, 83605

		Swales					
		Ponds					
Stormwater:		Borrow Ditche					
		Other, Explain	:				
Stormwater Management:	Does the	site disturb on	e or more acres of land? Yes No				
Fire Suppression Water Supply Source:							
Sources of Surface Water on or Nearby Properties (i.e., creeks, ditches, canals, lake, etc.):							
		Street Frontag	ne e				
Type of Site Access:		Easement Wic	Sth: Instrument #				
Street(s) Providing Access:							
Will Secondary Access for Fire be Provided:		Yes					
i iovided.	No Public						
	(Private)						
Internal Roads:	Internal Circulation						
		Road User's M	Maintenance Agreement Inst#				
		Caldwell Scho	ol District				
School Districts Serving this Location:		Vallivue School District					
SPECIAL ON-SITE CHARACTERISTICS	S						
	Yes	No	If yes, explain:				
Areas of Critical Environmental Concern?							
Evidence of Erosion?							
Fish Habitat?							
Floodplain?							
Riparian Vegetation?							
Steep Slopes?							
Streams/Creeks?							
Unique Animal/Plant Life?							
Unstable Soils?							
Wildlife Habitat?							
Historic Buildings or Features?							



621 Cleveland Blvd., Caldwell, Idaho, 83605 Phone: (208) 455-3021 | Web: <u>www.cityofcaldwell.org</u>

Describe characte	e any other unique site ristics:				
ACKNO	DWLEDGEMENT				
х	I acknowledge that all items of have been submitted as single-				all documents
х	I acknowledge that the applican subject sites prior to the public I City Codes; and				
Х	I acknowledge that the applican this application.	t or the applicant's	representative IS	REQUIRED to attend all p	ublic hearings for
I	certify this document has been a	cknowledged, signe	ed and dated by t	he:	
[☐ Property Owner as the Applic	ant 🗵	Property Owner'	s Agent / Representative	
Ā	Applicant / Applicant's Representa	ative Printed Name	Date		
- <i>F</i>	Applicant / Applicant's Representa	ative Signature			



Phone: (208) 455-3021 | Web: www.cityofcaldwell.org

REZONE CHECKLIST

The following items shall be included in the application submittal. Additional information may be required upon official review of the plans. Please check the box for each item listed below to confirm submission of the item listed.

SECTION 1: Filing Requirements

- All applications, checklists, plans and supporting documents must be submitted through our Online Permit Center.
- Filing fees (see Section 2 below)
- PDF Documents shall be formatted in accordance with Section 5 below.
- All documents shall follow the <u>naming conventions as shown here.</u>

SECTION 2: Filing Fees

Refer to the Department fee list for most current fees.

Application / Permit fees. Fees will be required to be paid once the application has been submitted and received by the department.

SECTION 3: Submittal Documents

The items listed below are considered a minimum. Additional information may be necessary for clarification during the review process.

- Master Land Use Application. Copy of a completed and signed master land use application.
- Application Checklist. Copy of a completed and signed application checklist
- Copy of Deeds or Proof of Ownership. If the owner is a corporation or LLC, proof of the representative or agent for the LLC or corporation will be required.
- Property Owner Acknowledgement. Signed Property Owner Acknowledgement form (if applicable)
- Neighborhood Meeting Information, including;

A copy of the letter sent to all owners, residents and associations within 500' of the property bounda	ry
A copy of the 500' mailing list	
A copy of the sign-in sheet, with your signature for certification	



Phone: (208) 455-3021 | Web: www.cityofcaldwell.org

- Legal Description and Exhibit. Attach a legal description of the property including metes and bounds to the centerline of all adjacent rights of ways. All legal descriptions shall be stamped and certified by a land surveyor registered to the State of Idaho and shall be accompanied by an exhibit stamped and certified by a land surveyor registered in the State of Idaho. For multiple parcels with different zoning designations, the legal descriptions and exhibit shall indicate the area for each zone, along with the acreage and boundaries.
- **Location / Vicinity Map.** Showing the boundaries of the subject property with relation to nearby roadways and landmarks.
- **X** Project Narrative. A detailed project narrative addressing the following:
 - Description of overall proposed rezone and future development plan.
 - Description of compliance with the City's Comprehensive Plan and Vision and compliance with zoning ordinances.
 - Description of overall project benefits, the impacts on surrounding properties, and the mitigation of those impacts.
- **Conceptual Development Plan** (If the rezone request is not associated with a special use permit, planned unit development or subdivision plat request).

SECTION 4: Project Specific Details

Fill in all the information below that is applicable to the project being proposed.

SUBJECT SITE LAND USE AN	D LAND USE INFORMATION					
Existing Zoning Designation:	R1					
Proposed Zoning Designation:	R2					
Existing City Comprehensive Plan Future Land Use Designation:	MDR					
Existing Land Use:	RESIDENTIAL					
Proposed Land Use:						
	RESIDENTIAL					



SURROUNDING LAND USE A	ND ZONING INFORMA	ATION	
	Existing Zoning Designation	Existing City Comp Plan Designation	Existing Use of Site
North of Subject Site:	Residential	MDR	Residential
South of Subject Site:	Residential	MDR	Residential
East of Subject Site:	Residential	MDR	Residential
West of Subject Site:	Residential	MDR	Residential

EXISTING UTILITIES, INFRASTR	UCTURI	E AND PUBLIC SERVICES INFORMATION				
	X	Street Frontage				
Type of Site Access:		Easement				
		Easement Width: Instrument #				
Street(s) Providing Access to Site:	Syri	ringa Ave. & Owhyee Ave.				
		Individual Domestic Well – How Many?				
		Centralized Public Water System				
Existing Domestic Water:	X	City Municipal Water System				
		N/A				
	Nearest Water Line Connection:					
		Individual Septic				
Existing Sewer (Wastewater):	X	City Municipal Sewer				
Existing Sewer (wastewater).		N/A				
	Nearest Sewer Line Connection:					
		Surface				
		Irrigation Well				
		Pressurized				
Existing Irrigation:	X	Gravity				
		N/A				
	Nearest Irrigation Connection:					
	Irrigatio	on District:				
		Caldwell School District				



School Districts Serving this	Vallivue School District
Location:	Nampa School District

CRITERIA FOR REZONE REQUEST
Please answer all of the questions below.
Please explain how the proposed zoning map amendment is consistent with the comprehensive plan's land use map, and the plan's established goals, objectives, and policies? Indicate which goals, objectives and policies it meets.
Please see narrative.
Please explain how the proposed map amendment is consistent with the purpose statement of the proposed zoning district as specified in Caldwell City Code.



Please see narrative.
Please explain how the intensity of development in the new zoning district will not create significant adverse impacts to
surrounding properties or the neighborhood or explain the impacts and how the impacts are proposed to be mitigated.
Please see narrative.
1 loads des hallauvel
Will adequate public facilities exist, or be provided, to serve all uses allowed on this property under the proposed zone?
Please explain.
Please see narrative.



Phone: (208) 455-3021 | Web: www.cityofcaldwell.org

SECTION 5: PDF Formatting Requirements

Portable Document Format (PDF) is the industry standard for electronic plans. The City of Caldwell only accepts PDF files for plan review. PDF files must be properly formatted as described below. Please read the instructions carefully. Improperly formatted plans can delay the plan review process for your project.

Layers: No multiple layers. Layers must be merged or flattened.


Format: Vector-based files are preferred given the ability to scale these files.

Resolution: Min. of 300 pixels per inch (PPI)

Grouping: Multiple sheet PDF (single file with multiple sheets)



Phone: (208) 455-3021 | Web: www.cityofcaldwell.org



plans.pdf (multiple sheets)

√ Correct

Labeling: Each sheet of the plans must be labeled with the project name, contractor, and address of the subject site.

SECTION 6: Applicant Acknowledgement

- I acknowledge that all items on the checklist are included in the submittal package and that all documents have been named accordingly and submitted as single-sided, high-resolution pdf documents; and
- 🛮 I acknowledge that I, the applicant, or my representative is responsible to attend all public hearings; and
- I acknowledge that applications are not deemed complete until the application has been submitted, all fees have been paid, and the application has been deemed accepted after completion of the prescreening process. This could impact neighborhood meeting deadlines and scheduling of public hearing dates.
- I acknowledge that I have read, understand, and am in compliance with all standards, terms, and requirements listed in Caldwell City Code; and
- I certify I am the:



□ Property Owner as the Applicant	X	Property Owner's Agent / Representative
Andrew Wheeler		9/22/25
Applicant / Applicant's Representative Printed Name		Name Date
Cendrew R Whalez		
Applicant / Applicant's Representative Sign	natur	 e



INVOICE

Permit #: SPP25-00008
Address: 0 Georgia AVE

Fee	Account Code	Amount
P&Z Fees - Preliminary Plat (Base Fee)	10180	2,688.00
P&Z Fees - Preliminary Plat (Add'l Fee of \$20.00 per lot, to include common lots)	10180	380.00
Fire Fees - Preliminary Plat (Base Fee)	22025	254.10
Fire Fees - Preliminary Plat (Add'l Fee of \$1.35 per lot to include common lots)	22025	25.65
Eng Fees - Preliminary Plat (Base Fee)	12511	675.28
Eng Fees - Preliminary Plat (Add'l Fee of \$22.51 per lot to include common lots)	12511	427.69
TOTAL	•	4,450.72



INVOICE

Permit #: ZON25-000004
Address: 0 Georgia AVE

Fee	Account Code	Amount
P&Z Fees - Rezone - 2 acres and More	10220	3,080.50
Fire Fees - Rezone - 50 acres or Less	22025	181.33
TOTAL	•	3,261.83



Andrew Wheeler 9201 W. State St. Ste. 102 Boise, ID 83714 andrew@thelandarchitect.com 855-787-6636 09/22/28

RE: Patriots Landing Development Planning & Zoning Commission City of Caldwell P.O. Box 1179 Caldwell, ID 83606

Re: Patriots Landing — Request for Rezone from R-1 to R-2 and Approval of a 23-Home Residential Development Serving Veterans

Dear Commissioners:

On behalf of the applicant/owner, we respectfully submit this narrative in support of Patriots Landing, a neighborhood of 23 attainable homes designed to serve Idaho veterans and their families. The site lies along Syringa Rd., with I-84 to the south (screened by the existing highway retaining wall), single-family residences to the east, and a single-family home plus an RV/metal shed storage use to the north/northeast adjacent to the site.

<u>Proposed Rezone and Development Plan:</u>

We request a rezone from R-1 (Residential Low Density) to R-2 (Residential Medium Density) to allow a modest increase in density and housing types consistent with surrounding development patterns and major transportation infrastructure.

Program summary:

- 23 dwelling units in 13 structures comprised of ten (10) duplex buildings (20 units) and three (3) detached single-unit homes (3 units).
- Homes are arranged on a shared lot/commons with private, fenced rear yards for each dwelling and common-area maintenance by an HOA (or similar association).
- A new public local street connection is proposed utilizing the existing right-of-way easement to improve circulation and emergency access.
- Open space is provided on the south portion of the site, integrated with a stormwater retention basin and informal recreation lawn.



• Building forms, heights, setbacks, landscaping, lighting, and parking will comply with the R-2 standards and applicable city development codes.

Veteran-serving intent:

Patriots Landing is purpose-built to welcome veterans through thoughtful design with durable materials, and HOA management of the common areas. We will coordinate with veteran-serving organizations during lease-up/sales to prioritize outreach and support.

Consistency with the Comprehensive Plan, Vision, and Zoning Ordinances:

Comprehensive Plan & Vision alignment

- Housing Choice & Attainability: Introduces duplex and small detached options that broaden the City's housing mix while remaining neighborhood-scale.
- Infill & Efficient Land Use: Converts an underutilized, vacant parcel near the I-84 corridor into productive housing with existing/planned utility and transportation capacity.
- Connectivity & Public Safety: Establishes a new public street connection for improved access, utility looping, and emergency response.
- Open Space & Stormwater: Delivers on-site common open space and on-site detention that meets City standards and protects downstream systems.
- Neighborhood Compatibility: utilizes two story single massing with the second floor stepped back, residential architecture, perimeter landscaping, and privacy fencing to transition sensitively to adjacent single-family homes.

Zoning compliance (R-2)

- Use: Duplex and detached single-family dwellings are permitted in R-2 zoning
- Dimensional standards: The site plan will be designed to meet or exceed R-2 setbacks, lot coverage, height, parking, landscaping, and fencing requirements.
- Access & circulation: The street section, sidewalks, and any private drive aisles will conform to City standards and Fire Code (turning radii, hydrant spacing, unobstructed width/height).
- Utilities & drainage: Water, sewer, and stormwater facilities will be designed per City/agency specifications; the south retention basin is sized to manage onsite runoff.
- Design quality: Materials, elevations, and lighting will comply with code and be reviewed with staff; lighting will be full cut-off and directed downward.

<u>Project Benefits, Potential Impacts, and Mitigation:</u>

Key public benefits

- Veteran-focused attainable housing in a small-neighborhood format.
- Infill development near regional transportation, reducing outward sprawl.
- New public street connection that improves block structure and safety.
- On-site open space and stormwater improvements.
- Neighborhood-scale design that complements adjacent single-family areas.



Potential impacts & mitigations:

- Traffic: A modest trip increase is expected for 23 homes; the new public connection disperses movements and enhances emergency access. Any warranted frontage or intersection improvements (signage, striping, curb/gutter/sidewalk) will be provided per City direction.
- Noise/visual: I-84 is buffered by the existing retaining wall. Within the project, privacy fencing and landscape buffers along edges will screen rear and side yards from neighbors.
- Stormwater: Managed on site in the south retention basin designed to City standards
- Construction: We will adhere to City noise hours, erosion and dust control measures, and maintain clear haul routes and safety signage.
- Neighborhood character: Building heights are residential scale; façades include varied materials, entries oriented to streets/paths, and garage/frontage treatments to avoid monotony.

Conclusion & Request:

Patriots Landing delivers the type of attainable, veteran-serving housing envisioned by the City's long-range plans, in a location where R-2 provides an appropriate, context-sensitive transition. The project upgrades local circulation, manages its stormwater responsibly, and integrates buffers and open space to respect adjacent homes.

We request your recommendation of approval for the R-1 to R-2 rezone and associated development approvals for Patriots Landing. We appreciate your consideration and look forward to collaborating with staff on final engineering and design details.

Regards,

Andrew Wheeler

Cendrew R wheeler

Architect

ARRANTS RICHARD M 2524 HILLCREST LN CALDWELL, ID, 83605

ASSEMBLY OF GOD CHURCH OF CALDWELL 821 N 16TH AVE CALDWELL, ID, 83605

BANUELOS DE LA CRUZ EULALIO 221 S GEORGIA AVE CALDWELL, ID, 83605 BARRAZA EDUARDO MARTINEZ 2623 OWYHEE ST CALDWEL, ID, 83605

BEIERLE MARK L 2306 CARTER CT CALDWELL, ID, 83605

BROTHERTON SCOTT 1130 PRINCETON RD WOODBURN, OR, 97071

CALDWEL, ID, 83605

BUCHANAN DOUGLAS 60192 HWY 26 JOHN DAY, OR, 97845 BURMEISTER WILLIAM A 203 S GEORGIA AVE CALDWELL, ID, 83605

BUTZ HELEN E REVOCABLE TRUST 2515 SYRINGA LN CALDWELL PACIFIC ASSOCIATES 430 E STATE ST STE 100 EAGLE, ID, 83616

2407 PARADISE CIR CALDWELL, ID, 83605

CANO ELVIA

CANTON REVOCABLE LIVING TRUST
115 S GEORGIA AVE
CALDWELL, ID, 83605

CHRISTENSEN JAMES W 2623 SYRINGA LN CALDWELL, ID, 83605 CRUZ BALDEMAR LOPEZ 215 S HOMEDALE AVE CALDWELL, ID, 83605

D AND D CONSTRUCTION SPECIALIST LLC 9424 SOUTHSIDE BLVD NAMPA, ID, 83686 DALE KAREN 2708 SYRINGA LN CALDWELL, ID, 83605 ESCOBEDO EDGAR ALFREDO 224 DEARBORN ST CALDWELL, ID, 83605

ESCOBEDO EDGAR ALFREDO 224 DEARBORN ST CALDWELL, ID, 83605 FERGUSON JOSEPH 2404 PARADISE CIR CALDWELL, ID, 83605 FUQUA CINDI R 2616 SYRINGA LN CALDWELL, ID, 83605

GEBHARDT KORYNNE L 2408 PARADISE CIR CALDWELL, ID, 83605 GROVE RUSSELL 2600 HILLCREST LN CALDWELL, ID, 83605 HANSON SHASTAANN M 2505 SYRINGA LN CALDWELL, ID, 83605

HARKINS STEVEN G 2413 SYRINGA LN CALDWELL, ID, 83605 HERNANDEZ ANDREA TERESA 2506 W MIDWEST DR TAYLORSVILLE, UT, 84129

421 HILL LN CALDWELL, ID, 83605

JAEGER JACOB M

JEWETT PHYLLIS J PO BOX 993 CALDWELL, ID, 83606 KASUMOVIC AHMET 2716 SYRINGA LN CALDWELL, ID, 83605

KING LAVERN D 316 22ND AVE S NAMPA, ID, 83651

LOTZ BARBARA J IRREVOCABLE TRUST KINNEY BAILEY M KINNEY BAILEY M 805 COLUMBIA AVE 314 HILL LN 314 HILL LN CALDWELL, ID, 83605 CALDWELL, ID, 83605 MOUNTAIN HOME, AR, 72653 MARIN CLAUDIO BENITEZ MTP ACQUISITION 460 FLORIDA LLC MTP ACQUISITION 520 FLORIDA LLC 2408 SYRINGA LN 3605 BRAHMS WAY 3605 BRAHMS WAY CALDWELL, ID, 83605 MISSOULA, MT, 59802 MISSOULA, MT, 59802 MTP ACQUISITION 520 FLORIDA LLC MTP ACQUISITION 520 FLORIDA LLC MTP ACQUISITION 520 FLORIDA LLC 3605 BRAHMS WAY 3605 BRAHMS WAY 3605 BRAHMS WAY MISSOULA, MT, 59802 MISSOULA, MT, 59802 MISSOULA, MT, 59802 MUHLENBECK ROBERT A MTP ACQUISITION 520 FLORIDA LLC MTP ACQUISTION 520 FLORIDA LLC 3605 BRAHMS WAY 3605 BRAHMS WAY 2324 SYRINGA LN MISSOULA, MT, 59802 MISSOULA, MT, 59802 CALDWELL, ID, 83605 NELSON GARRY W NORDBERG RICHARD A PACHECO JORGE PEREZ 2622 HILLCREST LN 2508 SYRINGA LN 2307 SYRINGA LN CALDWELL, ID, 83605 CALDWELL, ID, 83605 CALDWELL, ID, 83605 PATRIOT LANDING LLC PATRIOT LANDING LLC PATRIOT LANDING LLC 22493 DUFF LN 22493 DUFF LN 22493 DUFF LN MIDDLETON, ID, 83644 MIDDLETON, ID, 83644 MIDDLETON, ID, 83644 PATRIOT LANDING LLC PEGRAM LILLIE M PEREZ RAUL 22493 DUFF LN 114 S GEORGIA AVE 2413 PARADISE CIR MIDDLETON, ID, 83644 CALDWELL, ID, 83605 CALDWELL, ID, 83605 POUNDS DANIEL R SHORT KIRBY SILVA MAYRA 2703 SYRINGA LN 316 HILL LN 207 S HOMEDALE AVE CALDWELL, ID, 83605 CALDWELL, ID, 83605 CALDWELL, ID, 83605 SNOW DANIEL J SNYDER THOMAS A SNYDER THOMAS A 2310 CARTER CT 2305 SYRINGA LN 2310 CARTER CT CALDWELL, ID, 83605 CALDWELL, ID, 83605 CALDWELL, ID, 83605 SOUTHWESTERN IDAHO COOPERATIVE SNYDER THOMAS ALAN SNYDER THOMAS ALAN HOUSING AUTHORITY

2310 CARTER CT

CALDWELL, ID, 83605

377 CORNELL ST

MIDDLETON, ID, 83644

2310 CARTER CT

CALDWELL, ID, 83605

SOUTHWESTERN IDAHO COOPERATIVE TPC ENTERPRISE HOLDINGS LLC TAYLOR KATHERINE L HOUSING AUTHORITY 2403 PARADISE CIR 430 E STATE ST 377 CORNELL ST CALDWELL, ID, 83605 EAGLE, ID, 83616 MIDDLETON, ID, 83644 VAZQUEZ GONZALO L WARD DIANNA J WEBB CHARLES 121 S GEORGIA AVE 1403 ARLINGTON AVE 2314 HILLCREST LN CALDWELL, ID, 83605 CALDWELL, ID, 83605 CALDWELL, ID, 83605 WIDENER NADIA WILLIS ORVAL D ZUKIN JR CORPORATION DBA 2414 PARADISE CIR 2504 SYRINGA LN PO BOX 331

THE DALLES, OR, 97058

CALDWELL, ID, 83605

CALDWELL, ID, 83605

The Land Architect LLC 9201 W. State St. Ste. 102 Boise, ID 83713

RE: Rezone, Development Agreement & Preliminary Plat for a proposed subdivision at 2422 Syringa Ln, Caldwell, ID, 83605

To whom it may concern,

You are invited to a neighborhood meeting to discuss a project we are proposing near your property. The purpose of the meeting is to discuss the project, answer any questions, and listen to your feedback and suggestions.

Meeting Date: May 19th, 2025

Meeting Time: 4:00 pm

Meeting Location: Idaho Room Caldwell Public Library 1010 Dearborn St Caldwell ID 83605

Project Summary:

This project consists of a rezone, development agreement and preliminary plat application for a two story attached duplex single family and single family detached units in the City of Caldwell on a 2.88 acre parcel. The rezone will modify the existing zoning from R-1 (Low Density Residential) to R-2 (Medium Density Residential) and include (12) residential lots for (22) units.

If you would like to contact us ahead of the meeting, please feel free to reach out to us at 855-787-6636 or by email at andrew@thelandarchitect.com

VIETNAM AVENUE

Below is an illustration of our current site plan for the property which we will be discussing.

We look forward to hearing from you.

Thank you,

Andrew Wheeler Project Architect andrew@thelandarchitect.com 855-787-6636

NEIGHBORHOOD MEETING SIGN-IN FORM City of Caldwell Planning and Zoning Department 621 E. Cleveland Blvd., Caldwell, ID 83605 Phone: (208) 455-3021

Start Time of Neighborhood Meeting:_	B	4:00pm	
End Time of Neighborhood Meeting:_			

Those in attendance please print your name and address.

If no one attended, Applicant please write across this form "No one attended".

PRINTED NAME	ADDRESS, CITY, STATE, ZIP
1. Nick Snyder	2406 Syringa Caldrell JO 83605
2. Jonella Tewett	403 Hul Lin Caldwell 836
3. Jala Short	316 Hill Lin. Coldwell 7
4. Kerby Short	316 Hill In Cordwell
5. Raily linney	314 Hill In Caldwell Id
6. Comie Sudir	
7. Jan Snydtz	2406 Sypings / 2310 CARTENCT
8. Jarob Lancaster	1614 Blaine, coldwoll, In 83605
9. Cral Willis	2504 Syring Lane
10. Aharon willis	2504 Ayringa Lane
11	
12	
13	
14	
15	
16	

DATE

DENSITY = 7.63 UPA MAX. UNIT COUNT = (23)

SITE AREA = 139,360 SF

PARKING SUMMARY

REQUIRED: (2) PARKING STALLS PER APARTMENT UNIT (0.5) PARKING STALLS PER APARTMENT UNIT - GUEST PARKING TOTAL REQUIRED:

PER UNIT: (23) * (2) = (46) STALLS (23) * (0.5) = (12) GUEST STALLS TOTAL REQUIRED = (58) STALLS

PARKING STALL SIZE: 9 FT X 20 FT

PROVIDED: (46) GARAGE STALLS (46) UNCOVERED PARKING STALLS TOTAL PARKING STALLS PROVIDED = (92) STALLS

OPEN SPACE REQUIREMENTS

REQUIRED: 8% OF SITE AREA

PROJECT

SITE

SITE AREA = 139,360 * 0.08 **TOTAL REQUIRED OPEN SPACE = 11,**149 SF

TOTAL OPEN SPACE PROVIDED = 23,933 SF

SIGN

TLA 24-19

MORNING STAR DEVELOPMENT

SUDNE


ENTITLEMENT APPLICATION 09/22/25 LICENSED ARCHITECT AR-985897


> ANDREW R. WHEELER STATE OF IDAHO

SITE PLAN

A100







7,252 SF

LOT 9

7,252 SF

FOOTPRINT 1,470 SF

(2) COVERED STALLS

BUILDING TYPE A

OPEN SPACE

FIRE

TURNAROUND

6,468 SF

BUILDING TYPE C

6,638 SF

BUILDING TYPE C

SYRINGA LANE

FOOTPRINT 1,470 SF

FOOTPRINT 1,470 SF

BUILDING FOOTPRINT

1,470 SF

FOOTPRINT

BUILDING TYPE A

BUILDING TYPE A

BUILDING TYPE A

BUILDING TYPE A

PATRIOTS

R.R.O.W.

DRIVEWAY

R.R.O.W./

AVENE

SETBACK

SETBACK

LOT 1

10,138 SF

LOT 2

10,138 SF

LOT 3

LOT 4

10,138 SF

15'-0" 10,138 SF

LOT 9 = DUPLEX LOT (2) UNITS = 7,252 SF LOT 10 = DUPLEX LOT (2) UNITS = 7,252 SF LOT 12 = DUPLEX LOT (2) UNITS = 6,468 SF LOT 13 = DUPLEX LOT (2) UNITS = 6,638 SF LOT 14 = DUPLEX LOT (2) UNITS = 6,636 SF LOT 15 = DUPLEX LOT (2) UNITS = 6,467 SF LOT 16 = SINGLE-DETACHED LOT (1) UNITS = 5,940 SF

PLAN PREPARED BY APPLICANT

ANDREW@THELANDARCHITECT.COM

MIN. LOT AREA (INTERIOR LOT) = 6,000 SF

MIN. LOT AREA (CORNER LOT) = 7,500 SF

LOT 1 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 2 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 3 = DUPLEX LOT (2) UNITS = 10,138 SF LOT 4 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 5 = SINGLE-DETACHED LOT (1) UNIT = 8,705 SF LOT 8 = SINGLE-DETACHED LOT (1) UNITS = 4,758 SF

ZONING REQUIREMENTS

ANDREW WHEELER

9201 W.STATE ST. BOISE, ID 83714 855-787-6636

THE LAND ARCHITECT

ZONING DISTRICT: R-2 MAXIMUM HEIGHT: 35

MINIMUM SETBACKS:

REAR YARD = 15 FT

INTERIOR SIDE YARD = 6 FT STREET SIDE YARD = 15 FT

MIN. LOT FRONTAGE = 45 FT

FRONT = 20 FT

UNIT MIX

VICINITY MAP

SCALE: NTS

DATE

DENSITY = 7.63 UPA MAX. UNIT COUNT = (23)

SITE AREA = 139,360 SF

PARKING SUMMARY

REQUIRED: (2) PARKING STALLS PER APARTMENT UNIT (0.5) PARKING STALLS PER APARTMENT UNIT - GUEST PARKING TOTAL REQUIRED:

PER UNIT: (23) * (2) = (46) STALLS (23) * (0.5) = (12) GUEST STALLS TOTAL REQUIRED = (58) STALLS

PARKING STALL SIZE: 9 FT X 20 FT

PROVIDED: (46) GARAGE STALLS (46) UNCOVERED PARKING STALLS TOTAL PARKING STALLS PROVIDED = (92) STALLS

OPEN SPACE REQUIREMENTS

REQUIRED: 8% OF SITE AREA

PROJECT

SITE

SITE AREA = 139,360 * 0.08 **TOTAL REQUIRED OPEN SPACE = 11,**149 SF

TOTAL OPEN SPACE PROVIDED = 23,933 SF

SIGN

TLA 24-19

MORNING STAR DEVELOPMENT

SUDNE


ENTITLEMENT APPLICATION 09/22/25 LICENSED ARCHITECT AR-985897


> ANDREW R. WHEELER STATE OF IDAHO

SITE PLAN

A100







7,252 SF

LOT 9

7,252 SF

FOOTPRINT 1,470 SF

(2) COVERED STALLS

BUILDING TYPE A

OPEN SPACE

FIRE

TURNAROUND

6,468 SF

BUILDING TYPE C

6,638 SF

BUILDING TYPE C

SYRINGA LANE

FOOTPRINT 1,470 SF

FOOTPRINT 1,470 SF

BUILDING FOOTPRINT

1,470 SF

FOOTPRINT

BUILDING TYPE A

BUILDING TYPE A

BUILDING TYPE A

BUILDING TYPE A

PATRIOTS

R.R.O.W.

DRIVEWAY

R.R.O.W./

AVENE

SETBACK

SETBACK

LOT 1

10,138 SF

LOT 2

10,138 SF

LOT 3

LOT 4

10,138 SF

15'-0" 10,138 SF

LOT 9 = DUPLEX LOT (2) UNITS = 7,252 SF LOT 10 = DUPLEX LOT (2) UNITS = 7,252 SF LOT 12 = DUPLEX LOT (2) UNITS = 6,468 SF LOT 13 = DUPLEX LOT (2) UNITS = 6,638 SF LOT 14 = DUPLEX LOT (2) UNITS = 6,636 SF LOT 15 = DUPLEX LOT (2) UNITS = 6,467 SF LOT 16 = SINGLE-DETACHED LOT (1) UNITS = 5,940 SF

PLAN PREPARED BY APPLICANT

ANDREW@THELANDARCHITECT.COM

MIN. LOT AREA (INTERIOR LOT) = 6,000 SF

MIN. LOT AREA (CORNER LOT) = 7,500 SF

LOT 1 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 2 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 3 = DUPLEX LOT (2) UNITS = 10,138 SF LOT 4 = DUPLEX LOT (2) UNITS = 10,138 SF

LOT 5 = SINGLE-DETACHED LOT (1) UNIT = 8,705 SF LOT 8 = SINGLE-DETACHED LOT (1) UNITS = 4,758 SF

ZONING REQUIREMENTS

ANDREW WHEELER

9201 W.STATE ST. BOISE, ID 83714 855-787-6636

THE LAND ARCHITECT

ZONING DISTRICT: R-2 MAXIMUM HEIGHT: 35

MINIMUM SETBACKS:

REAR YARD = 15 FT

INTERIOR SIDE YARD = 6 FT STREET SIDE YARD = 15 FT


MIN. LOT FRONTAGE = 45 FT

FRONT = 20 FT

UNIT MIX

VICINITY MAP

SCALE: NTS






BUILDING TYPE A -COOL TONE




BUILDING TYPE A - WARM TONE





10. DETACHED WOOD PATIO COVER

GARAGE DOOR

COLUMN POST, AND BEAM REFER TO BUILDING CROSS SECTIONS &








TLA 24-19

CLIENT TIM DAVIS

DRY STACK LEDGE STONE OR EQUAL

MASONRY TO MATCH "OLD WORLD LEDGE" DRY STACK LEDGE STONE OR EQUAL

ENTITLEMENT APPLICATION 09/22/25



BUILDING TYPE A - MATERIALS BOARD

A203

SCALE

As indicated



BUILDING TYPE B -COOL TONE




BUILDING TYPE B - WARM TONE

KEY NOTES -30 YEAR TYPE 'A' COMPOSITE SHINGLE FIBER CEMENT SIDING OR APPROVED EQUAL BOARD AND BATTEN SIDING OR APPROVED EQUAL WHITE VINYL WINDOWS PRE-FINISHED METAL GUTTER, SEE ROOF PLAN FOR EXTENT. DOWNSPOUT TO MATCH COLOR MASONRY WALL VEENER, SET IN MORTAR BED WITH FLASHING AND


> GARAGE DOOR 12. ROOF VENT

10. DETACHED WOOD PATIO COVER






REVISION



TLA 24-19

CLIENT TIM DAVIS



BUILDING TYPE B - MATERIALS BOARD

A203.1

As indicated



BUILDING TYPE C -COOL TONE




BUILDING TYPE C - WARM TONE

KEY NOTES -30 YEAR TYPE 'A' COMPOSITE SHINGLE FIBER CEMENT SIDING OR APPROVED EQUAL BOARD AND BATTEN SIDING OR APPROVED EQUAL WHITE VINYL WINDOWS PRE-FINISHED METAL GUTTER, SEE ROOF PLAN FOR EXTENT. DOWNSPOUT TO MATCH COLOR 1" FINISH FASCIA MASONRY WALL VEENER, SET IN MORTAR BED WITH FLASHING AND WEEP SCREED 10. DETACHED WOOD PATIO COVER

GARAGE DOOR

12. ROOF VENT





REVISION

BUILDING TYPE C - MATERIALS BOARD

ANDREW R. WHEELER

STATE OF IDAHO

LICENSED

ARCHITECT AR-985897

A203.2

SCALE

As indicated

DATE

TLA 24-19

CLIENT MORNING STAR DEVELOPMENT

18. STORM DRAINAGE FACILITIES MUST BE PROTECTED FROM ANY AND ALL CONTAMINATION DURING THE CONSTRUCTION AND INSTALLATION OF THE LANDSCAPE IRRIGATION SYSTEM.

1. ALL AREAS TO BE PLANTED OR HYDROSEEDED SHALL HAVE WEED ABATEMENT OPERATIONS PERFORMED ON THEM PRIOR TO PLANTING OR HYDROSEEDING. CONTRACTOR SHALL SPRAY ALL EXPOSED WEEDS WITH "ROUND-UP" (CONTACT HERBICIDE) OR

APPROVED EQUAL.

CONTRACTOR SHALL OPERATE THE AUTOMATIC IRRIGATION SYSTEM FOR A PERIOD OF FOURTEEN (14) DAYS. AT CONCLUSION OF THIS WATERING PERIOD, DISCONTINUE WATERING FOR THREE TO FIVE (3-5) 5. APPLY SECOND APPLICATION OF "ROUND-UP" TO ALL EXPOSED WEEDS. APPLY IN STRICT CONFORMANCE

WITH MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS. DO NOT WATER FOR AT LEAST SEVEN (7) 6. IF ANY EVIDENCE OF WEED GERMINATION EXISTS AFTER TWO (2) APPLICATIONS, CONTRACTOR SHALL BE

INSURES COMPLETE COVERAGE AND PROPERLY ZONED FOR REQUIRED WATER USES. EACH HYDROZONE IS TO BE IRRIGATED WITH SEPARATE INDIVIDUAL STATIONS. PLANTER BEDS AND LAWN AREAS ARE TO HAVE SEPARATE HYDRO-ZONES.

PLANTER BEDS ARE TO HAVE DRIP IRRIGATION SYSTEM OR POP-UP SPRAY SYSTEM. ANNUALS,

PERENNIALS GROUND COVERS OR SHRUB MASSINGS SHALL HAVE A POP-UP SPRAY SYSTEM. ELECTRONIC WATER DISTRIBUTION/ TIMING CONTROLLERS ARE TO BE PROVIDED. MINIMUM CONTROLLER REQUIREMENTS ARE AS FOLLOWS:

c. AT LEAST ONE PROGRAM FOR EACH HYDROZONE d. SUFFICIENT MULTIPLE CYCLES TO AVOID WATER RUN-OFF

INDIVIDUAL VALVE WATERING STATIONS WILL BE DESIGNED AND INSTALLED TO PROVIDE WATER TO RESPECTIVE HYDRO-ZONES. THE IRRIGATION SYSTEM SHALL BE DESIGNED TO PROVIDE 100% HEAD TO HEAD COVERAGE WITH

(BUILDINGS, SIDEWALKS, DRIVEWAYS, AND ASPHALT AREAS).

PROVIDE MINIMUM (1) QUICK COUPLER VALVE PER EACH (6) AUTOMATIC VALVE ZONES. APPROVE Q.C.V. LOCATIONS WITH LANDSCAPE ARCHITECT.

LANDSCAPE NOTES:

- 1. CONTRACTOR SHALL REPORT TO LANDSCAPE ARCHITECT ALL CONDITIONS WHICH IMPAIR AND/OR PREVENT THE PROPER EXECUTION OF THIS WORK, PRIOR TO BEGINNING WORK.
- NO MATERIAL SUBSTITUTIONS SHALL BE MADE WITHOUT THE LANDSCAPE ARCHITECT'S PRIOR WRITTEN APPROVAL. ALTERNATE MATERIALS OF SIMILAR SIZE AND CHARACTER MAY BE CONSIDERED IF SPECIFIED PLANT MATERIALS CAN NOT BE OBTAINED. COORDINATE ALL WORK WITH ALL OTHER SITE RELATED DEVELOPMENT DRAWINGS.
- COORDINATE WORK SCHEDULE AND OBSERVATIONS WITH LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION START-UP.
- ALL PLANT MATERIAL SHALL BE INSTALLED AS PER DETAILS. ALL PLANT MATERIAL SHALL CONFORM TO THE AMERICAN NURSERYMAN STANDARDS FOR TYPE AND SIZE SHOWN. PLANTS WILL BE REJECTED IF NOT IN A SOUND AND HEALTHY CONDITION.
- IN THE EVENT OF A PLANT COUNT DISCREPANCY, PLANT SYMBOLS SHALL OVERRIDE SCHEDULE QUANTITIES AND CALL OUT SYMBOL NUMBERS.
- ALL PLANTING BEDS SHALL BE COVERED WITH A MINIMUM OF 3" DEPTH OF 3/4" MINUS BLACK AND TAN PERMA BARK ROCK MULCH OVER TOPSOIL AS SPECIFIED. SUBMIT SAMPLE FOR APPROVAL. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR BEGINNING AT THE DATE OF ACCEPTANCE BY THE OWNER, REPLACE ALL PLANT MATERIAL FOUND DEAD OR NOT IN A HEALTHY
- CONDITION IMMEDIATELY WITH THE SAME SIZE AND SPECIES AT NO COST TO THE OWNER. 10. FINISH GRADES SHALL PROVIDE A SMOOTH TRANSITION WITH ADJACENT SURFACES AND ENSURE POSITIVE DRAINAGE IN ACCORDANCE WITH THE SITE CIVIL GRADING PLAN.
- AMEND EXISTING APPROVED TOPSOIL AT A RATIO OF THREE CUBIC YARDS OF APPROVED COMPOST PER 1000 SQUARE FEET. ROTO-TILL ORGANIC MATTER A MINIMUM OF 6 INCHES INTO TOPSOIL.
- 12. FERTILIZE ALL TREES AND SHRUBS WITH 'AGRIFORM' PLANTING TABLETS. QUANTITY PER
- MANUFACTURER'S RECOMMENDATIONS. 13. ALL PLANTING BEDS SHALL HAVE A MINIMUM 18" DEPTH OF TOPSOIL. LAWN AREAS SHALL HAVE A MINIMUM 12" DEPTH OF TOPSOIL. SPREAD, COMPACT, AND FINE GRADE TOPSOIL TO A SMOOTH AND
- SURFACES OF TURF SOD AREAS, AND 1" BELOW ADJACENT SURFACES OF TURF SEED AREAS. REUSE EXISTING TOPSOIL STOCKPILED ON THE SITE. SUPPLEMENT WITH IMPORTED TOPSOIL WHEN QUANTITIES ARE INSUFFICIENT. VERIFY SUITABILITY AND CONDITION OF TOPSOIL AS A GROWING MEDIUM. PERFORM SOIL TEST/ ANALYSIS AND PROVIDE ADDITIONAL AMENDMENT AS DETERMINED BY SOIL TESTS. TOPSOIL SHALL BE A LOOSE, FRIABLE, SANDY LOAM, CLEAN AND FREE OF TOXIC MATERIALS, NOXIOUS WEEDS, WEED SEEDS, ROCKS, GRASS OR OTHER FOREIGN MATERIAL AND A HAVE A PH OF 5.5 TO 7.0. IF ONSITE TOPSOIL DOES NOT MEET THESE MINIMUM STANDARDS, CONTRACTOR IS RESPONSIBLE TO

UNIFORM GRADE 3" BELOW ADJACENT SURFACES OF PLANTER BED AREAS, 1-1/2" BELOW ADJACENT

- A) PROVIDE APPROVED IMPORTED TOPSOIL, OR B) IMPROVE ON-SITE TOPSOIL WITH METHODS APPROVED BY THE LANDSCAPE ARCHITECT.
- 15. IF IMPORTED TOPSOIL FROM OFF-SITE SOURCES IS REQUIRED, ENSURE IT IS FERTILE, FRIABLE, NATURAL LOAM, SURFACE SOIL, REASONABLY FREE OF SUBSOIL, CLAY LUMPS, BRUSH, WEEDS AND OTHER LITTER, AND FREE OF ROOTS, STUMPS, STONES LARGER THAN 2 INCHES IN ANY DIMENSION, AND OTHER EXTRANEOUS OR TOXIC MATTER HARMFUL TO PLANT GROWTH.
- A) OBTAIN TOPSOIL FROM LOCAL SOURCES OR FROM AREAS HAVING SIMILAR SOIL CHARACTERISTICS TO THOSE FOUND ON THE PROJECT SITE. OBTAIN TOPSOIL ONLY FROM NATURALLY, WELL-DRAINED SITES WHERE TOPSOIL OCCURS AT A DEPTH OF NOT LESS THAN 4 INCHES. B) REPRESENTATIVE SAMPLES SHALL BE TESTED FOR ACIDITY, FERTILITY, TOXICITY, AND GENERAL TEXTURE BY A RECOGNIZED COMMERCIAL OR GOVERNMENT AGENCY AND COPIES OF THE TESTING AGENCY'S FINDINGS AND RECOMMENDATIONS SHALL BE FURNISHED TO THE OWNER'S REPRESENTATIVE BY THE CONTRACTOR. NO TOPSOIL SHALL BE DELIVERED IN A FROZEN OR MUDDY CONDITION. ACIDITY/ALKALINITY RANGE - PH. 5.5 TO 7.6.
- 16. IMMEDIATELY CLEAN UP ANY TOPSOIL OR OTHER DEBRIS ON THE SITE CREATED FROM LANDSCAPE OPERATIONS AND DISPOSE OF PROPERLY OFF SITE.
- 17. TREES SHALL NOT BE PLANTED WITHIN THE 10'-0" CLEAR ZONE OF ALL STORM DRAIN PIPE, STRUCTURES,
- IN THE EVENT OF A DISCREPANCY, NOTIFY THE LANDSCAPE ARCHITECT IMMEDIATELY.

WEED ABATEMENT NOTES:

- - DO NOT WATER FOR AT LEAST SEVEN (7) DAYS. REMOVE EXPOSED WEEDS FROM THE SITE.
 - DAYS. REMOVE WEEDS FROM THE SITE.
- DIRECTED TO PERFORM A THIRD APPLICATION. 7. AT THE TIME OF PLANTING AND HYDROSEEDING, ALL PLANTING AREAS SHALL BE WEED FREE.

IRRIGATION NOTES:

1. ALL LANDSCAPED AREAS SHALL HAVE AN AUTOMATIC UNDERGROUND SPRINKLER SYSTEM WHICH

POP-UP SPRINKLER HEADS SHALL HAVE A MINIMUM RISER HEIGHT OF 4 INCHES AT LAWN AREAS AND 18"

a. PRECISE INDIVIDUAL STATION TIMING b. RUN TIME CAPABILITIES FOR EXTREMES IN PRECIPITATION RATES

e. POWER FAILURE BACKUP FOR ALL PROGRAMMED INDIVIDUAL VALVE WATERING STATIONS WILL BE

DESIGNED AND INSTALLED TO PROVIDE WATER TO RESPECTIVE HYDRO-ZONES.

TRIANGULAR SPACING. SPRINKLER HEADS SHALL BE ADJUSTED TO REDUCE OVER SPRAY ONTO IMPERVIOUS SURFACES

ENTITLEMENT APPLICATION

05/02/25

OVERALL PRELIMINARY LANDSCAPE PLAN

SCALE

1/32" = 1'-0"



/10,138 SF

Block

—SYRINGA LANE -

10,138 SF

10-02-09-4 COMMON OPEN SPACE REQUIREMENTS AND STANDARDS; 10-02-09-5 STREET LANDSCAPE BUFFERS 10-02-09-6BUFFERS BETWEEN DIFFERENT LAND USES; 10-02-09-7 PATHWAY LANDSCAPING STANDARDS TOTAL SITE AREA: 139,360 SF

LANDSCAPE REQUIREMENTS

LANDSCAPE COVERAGE: - SF - 14.9% MINIMUM PLANT SIZES SHALL BE USED: **EVERGREEN TREES:**

ORNAMENTAL TREES: 2" CALIPER SHADE TREES: 2" CALIPER WOODY SHRUBS: 2 GALLON

NUMBER OF TREES PROPOSED: 6 (0 EXISTING/6 PROPOSED)

COMMON OPEN SPACE: PROPOSED AVERAGE LOT SIZE: 7,995.15 SF

REQUIRED % OF OPEN SPACE: 11,149 SF - 8% PROVIDED % OF OPEN SPACE: 27,726.34 SF - 15.16%

1 TREE PER 5,000 S.F. OF AREA, AT LEAST 50% OF REQUIRED TREES SHALL BE CLASS II/III REQUIRED TREES: 6 PROVIDED TREES: 6

9,520 SF

<-SS---- EX-SS---- EX-SS----

_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _

7,056 SF

APPLICABLE CITY OF CALDWELL, IDAHO CODE: 10-02-09-3 LANDSCAPE CRITERIA AND INSTALLATION PRACTICES;

STREET LANDSCAPE BUFFERS: 1 CLASS I TREE PER 25 LIN. FT 1 CLASS II TREE PER 35 LIN. FT.

1 SHRUB PER 4 LIN. FT. OF BUFFER AREA NO MORE THAN 40% OF REQUIRED TREES TO BE OF SAME SPECIES, NO MORE THAN 50% OF REQUIRED TREES SHALL BE CLASS I

SYRINGA LANE (LOCAL): NO LANDSCAPE BUFFER REQUIRED

S. GEORGIA AVENUE (LOCAL): NO LANDSCAPE BUFFER REQUIRED

BUFFERS BETWEEN DIFFERENT LAND USES: NO LANDSCAPE BUFFER REQUIRED

Block 2


PRELIMINARY LANDSCAPE PLAN

CALL 2 BUSINESS DAYS
IN ADVANCE BEFORE
YOU DIG, GRADE, OR
EXCAVATE FOR THE
MARKING OF
UNDERGROUND
MEMBER UTILITIES

PLANTS TO BE INSTALLED

DATE


ENTITLEMENT APPLICATION 05/02/25



PRELIMINARY LANDSCAPE PLAN -AREA ONE

L1.1

1/32" = 1'-0" SCALE



PLANT SCHEDULE

DECIDUOUS TREES

FLOWERING TREES

ORNAMENTAL GRASSES

PERENNIALS

COMMON / BOTANICAL NAME

Acer truncatum x platanoides 'Warrenred' TM

2" Cal. B&B

Pacific Sunset Maple

Bloodgood London Plane Tree

Platanus x acerifolia 'Bloodgood'

Village Green Japanese Zelkova

Zelkova serrata 'Village Green'

Canada Red Chokecherry

Slowmound Mugo Pine

Pinus mugo 'Slowmound'

Flower Carpet Pink Rose

Spiraea japonica 'Neon Flash'

Heavy Metal Switch Grass

Grasspave Porous Grass Paver

1" minus Small Bark Mulch

RTF Sod Rhizomatous Tall Fescue

Karl Foerster Feather Reed Grass

Panicum virgatum 'Heavy Metal' Shenandoah Switch Grass

Panicum virgatum 'Shenandoah'

Leading Lady Amethyst Bee Balm Monarda x 'Leading Lady Amethyst'

COMMON / BOTANICAL NAME

Calamagrostis x acutiflora 'Karl Foerster'


Rosa x 'Noatraum' Neon Flash Spirea

Otto Luyken English Laurel


Prunus laurocerasus 'Otto Luyken'

Prunus virginiana 'Canada Red'

COMMON / BOTANICAL NAME




PRELIMINARY LANDSCAPE PLAN - AREA ONE



REVISION

DATE



TLA 24-19 MORNING STAR DEVELOPMENT

ENTITLEMENT APPLICATION 05/02/25



PRELIMINARY LANDSCAPE PLAN -AREA TWO

L1.2

SCALE

1/32" = 1'-0"

PREVAILING WIND DIRECTION

LEADER!!

RUBBER CINCH TIE

PREVAILING WIND.

SPECIFIED.

FROM TRUNK.

TABLETS

- TOP OF GRASS ROOT MASS 6 MM (1/4") ABOVE TOP OF RING.

- GRASSPAVE 2 ATTACH WITH PEG AND HOLE.

COMPACTED SANDY GRAVEL BASE COURSE.

CONCRETE SAND (CLEAN, SHARP SAND)

— COMPACTED SANDY GRAVEL ROAD BASE - 6" DEPTH.

COMPACTED SUBGRADE, 95% MODIFIED PROCTOR DENSITY

-ROOT MASS TO FILL GRASSPAVE 2.

HYDROGROW MIX BELOW RING SUPPLIED FREE BY MANUFACTURER.

- AFTER INSTALLATION

2"x 2" WOOD STAKE (LENGTH AS

REQUIRED)-DO NOT PENETRATE ROOTBALL
 SEE NOTE 1. SET STAKES PARALLEL TO

REMOVE TREE WRAP TRUNK PROTECTION,

CONSTRUCT 2" EARTH BERM AT EDGE OF ROOTBALL, FILL TREE RING W/ MULCH, AS

- COMMERCIAL SLOW RELEASE FERTILIZER

- BACKFILL WITH APPROVED TOPSOIL AND SOIL AMENDMENTS AS SPECIFIED. BACKFILL IN 6" LIFTS, WATER EACH LAYER, TAMP LIGHTLY AS REQUIRED, BACKFILL

SET ROOTBALL ON NATIVE, UNDISTURBED


- SIDES OF HOLE ROUGH & UNEVEN

SOIL EVEN W/ TOP OF ROOTBALL,

3" THICK MULCH LAYER, KEEP MULCH 3" AWAY

- REMOVE DEAD/DAMAGED BRANCHES AND PRUNE TO INTERNATIONAL SOCIETY OF ARBORICULTURE STANDARDS; IMPROPERLY PRUNED TREES (AS DETERMINED BY THE LANDSCAPE ARCHITECT) SHALL BE REMOVED AND REPLACED. DO NOT REMOVE MAIN

DATE




TLA 24-19 CLIENT MORNING STAR DEVELOPMENT

ENTITLEMENT APPLICATION 05/02/25




PRELIMINARY LANDSCAPE **DETAILS**

SCALE



PLANTER BED CUT EDGE (TYPICAL AT TREES IN TURF AREAS) NOT TO SCALE



- SHRUB SHALL BEAR SAME RELATIONSHIP TO GRADE AS IT DID IN NURSERY. WATER SHRUB TWICE WITHIN FIRST 24 HOURS.
- THIN BRANCHES AND FOLIAGE BY $\frac{1}{3}$. DO NOT CUT LEADERS TO RETAIN NATURAL SHRUB SHAPE.
- FOR CONTAINER GROWN PLANTS THAT ARE ROOTBOUND, SPLIT THE ROOTBALL WITH 3 EQUAL SPACED

SHRUB PLANTING

NOT TO SCALE

NOTES:

WARRANTY PERIOD.

ARCHITECT BEFORE PROCEEDING.

WATER TREE TWICE WITHIN THE FIRST 24 HOURS.

GRASSPAVE SECTION

-ROOT FLARE TO BE AT SOIL LINE

The state of the s

WIDTH | WIDTH | WIDTH \

BIODEGRADABLE BURLAP SHALL BE LEFT ON THE BOTTOM OF THE ROOTBALL

OF BALL OF BALL OF BALL OF BALL SOIL EVEN W/ TOP OF ROOT DO NOT OVER COMPACT!!

REMOVE BURLAP, TWINE, AND WIRE BASKET FROM TOP % OF ROOTBALL. REMOVE ALL NAILS, TIES, AND PLASTIC FROM ROOTBALL. IF SYNTHETIC BURLAP IS UTILIZED TO WRAP THE ROOTBALL, IT SHALL BE COMPLETELY REMOVED. ONLY

AFTER SUBSTANTIAL COMPLETION WHICHEVER IS GREATER. ALL STAKING SHALL BE REMOVED AT THE END OF THE

3. IN THE EVENT OF A QUESTION OR LACK OF CLARITY ON THE DRAWINGS, THE CONTRACTOR IS TO NOTIFY THE LANDSCAPE

LANDSCAPE CONTRACTOR IS TO NOTIFY THE LANDSCAPE ARCHITECT AND OWNER PRIOR TO INSTALLATION OF PLANT

#24-2 OR APPROVED EQUAL). LOCATE ROOT BARRIER AT BACK OF CURB AND EDGE OF SIDEWALK. ALL TREE INSTALLATIONS SHALL CONFORM TO ALL AGENCY APPROVAL REQUIREMENTS, CONTRACTOR SHALL VERIFY PRIOR TO ANY INSTALLATIONS.

SEE ENLARGEMENT

METHOD. SECURE THE TIES TO THE STAKES WITH GALVANIZED NAILS TO PREVENT SLIPPAGE.


DECIDUOUS TREE PLANTING

NOT TO SCALE

NOT TO SCALE

2. THE STAKING OF TREES IS TO BE THE CONTRACTOR'S OPTION: HOWEVER, THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL TREES ARE PLANTED STRAIGHT AND THAT THEY REMAIN STRAIGHT FOR LENGTH OF WARRANTY PERIOD OR 1 YEAR

WRAP RUBBER CINCH TIES AROUND THE TREE TRUNKS AND STAKES USING EITHER THE STANDARD OR FIGURE EIGHT TYING IN THE EVENT HARDPAN SOILS PREVENT TREE PLANTING AS DETAILED, NOTIFY THE LANDSCAPE ARCHITECT IMMEDIATELY. FOR TREES LOCATED WITHIN ROADSIDE PLANTERS LESS THAN 8'-0" IN WIDTH, PROVIDE TREE ROOT BARRIER (DEEPROOT



1/32" = 1'-0"

DATE

ENTITLEMENT APPLICATION 05/02/25




OPEN SPACE EXHIBIT

L1.6

SCALE 1/32" = 1'-0"





DATE

TLA 24-19

CLIENT MORNING STAR DEVELOPMENT

18. STORM DRAINAGE FACILITIES MUST BE PROTECTED FROM ANY AND ALL CONTAMINATION DURING THE CONSTRUCTION AND INSTALLATION OF THE LANDSCAPE IRRIGATION SYSTEM.

1. ALL AREAS TO BE PLANTED OR HYDROSEEDED SHALL HAVE WEED ABATEMENT OPERATIONS PERFORMED ON THEM PRIOR TO PLANTING OR HYDROSEEDING. CONTRACTOR SHALL SPRAY ALL EXPOSED WEEDS WITH "ROUND-UP" (CONTACT HERBICIDE) OR

APPROVED EQUAL.

CONTRACTOR SHALL OPERATE THE AUTOMATIC IRRIGATION SYSTEM FOR A PERIOD OF FOURTEEN (14) DAYS. AT CONCLUSION OF THIS WATERING PERIOD, DISCONTINUE WATERING FOR THREE TO FIVE (3-5) 5. APPLY SECOND APPLICATION OF "ROUND-UP" TO ALL EXPOSED WEEDS. APPLY IN STRICT CONFORMANCE

WITH MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS. DO NOT WATER FOR AT LEAST SEVEN (7) 6. IF ANY EVIDENCE OF WEED GERMINATION EXISTS AFTER TWO (2) APPLICATIONS, CONTRACTOR SHALL BE

INSURES COMPLETE COVERAGE AND PROPERLY ZONED FOR REQUIRED WATER USES. EACH HYDROZONE IS TO BE IRRIGATED WITH SEPARATE INDIVIDUAL STATIONS. PLANTER BEDS AND LAWN AREAS ARE TO HAVE SEPARATE HYDRO-ZONES.

PLANTER BEDS ARE TO HAVE DRIP IRRIGATION SYSTEM OR POP-UP SPRAY SYSTEM. ANNUALS,

PERENNIALS GROUND COVERS OR SHRUB MASSINGS SHALL HAVE A POP-UP SPRAY SYSTEM. ELECTRONIC WATER DISTRIBUTION/ TIMING CONTROLLERS ARE TO BE PROVIDED. MINIMUM CONTROLLER REQUIREMENTS ARE AS FOLLOWS:

c. AT LEAST ONE PROGRAM FOR EACH HYDROZONE d. SUFFICIENT MULTIPLE CYCLES TO AVOID WATER RUN-OFF

INDIVIDUAL VALVE WATERING STATIONS WILL BE DESIGNED AND INSTALLED TO PROVIDE WATER TO RESPECTIVE HYDRO-ZONES. THE IRRIGATION SYSTEM SHALL BE DESIGNED TO PROVIDE 100% HEAD TO HEAD COVERAGE WITH

(BUILDINGS, SIDEWALKS, DRIVEWAYS, AND ASPHALT AREAS).

PROVIDE MINIMUM (1) QUICK COUPLER VALVE PER EACH (6) AUTOMATIC VALVE ZONES. APPROVE Q.C.V. LOCATIONS WITH LANDSCAPE ARCHITECT.

LANDSCAPE NOTES:

- 1. CONTRACTOR SHALL REPORT TO LANDSCAPE ARCHITECT ALL CONDITIONS WHICH IMPAIR AND/OR PREVENT THE PROPER EXECUTION OF THIS WORK, PRIOR TO BEGINNING WORK.
- NO MATERIAL SUBSTITUTIONS SHALL BE MADE WITHOUT THE LANDSCAPE ARCHITECT'S PRIOR WRITTEN APPROVAL. ALTERNATE MATERIALS OF SIMILAR SIZE AND CHARACTER MAY BE CONSIDERED IF SPECIFIED PLANT MATERIALS CAN NOT BE OBTAINED. COORDINATE ALL WORK WITH ALL OTHER SITE RELATED DEVELOPMENT DRAWINGS.
- COORDINATE WORK SCHEDULE AND OBSERVATIONS WITH LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION START-UP.
- ALL PLANT MATERIAL SHALL BE INSTALLED AS PER DETAILS. ALL PLANT MATERIAL SHALL CONFORM TO THE AMERICAN NURSERYMAN STANDARDS FOR TYPE AND SIZE SHOWN. PLANTS WILL BE REJECTED IF NOT IN A SOUND AND HEALTHY CONDITION.
- IN THE EVENT OF A PLANT COUNT DISCREPANCY, PLANT SYMBOLS SHALL OVERRIDE SCHEDULE QUANTITIES AND CALL OUT SYMBOL NUMBERS.
- ALL PLANTING BEDS SHALL BE COVERED WITH A MINIMUM OF 3" DEPTH OF 3/4" MINUS BLACK AND TAN PERMA BARK ROCK MULCH OVER TOPSOIL AS SPECIFIED. SUBMIT SAMPLE FOR APPROVAL. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR BEGINNING AT THE DATE OF ACCEPTANCE BY THE OWNER, REPLACE ALL PLANT MATERIAL FOUND DEAD OR NOT IN A HEALTHY
- CONDITION IMMEDIATELY WITH THE SAME SIZE AND SPECIES AT NO COST TO THE OWNER. 10. FINISH GRADES SHALL PROVIDE A SMOOTH TRANSITION WITH ADJACENT SURFACES AND ENSURE POSITIVE DRAINAGE IN ACCORDANCE WITH THE SITE CIVIL GRADING PLAN.
- AMEND EXISTING APPROVED TOPSOIL AT A RATIO OF THREE CUBIC YARDS OF APPROVED COMPOST PER 1000 SQUARE FEET. ROTO-TILL ORGANIC MATTER A MINIMUM OF 6 INCHES INTO TOPSOIL.
- 12. FERTILIZE ALL TREES AND SHRUBS WITH 'AGRIFORM' PLANTING TABLETS. QUANTITY PER
- MANUFACTURER'S RECOMMENDATIONS. 13. ALL PLANTING BEDS SHALL HAVE A MINIMUM 18" DEPTH OF TOPSOIL. LAWN AREAS SHALL HAVE A MINIMUM 12" DEPTH OF TOPSOIL. SPREAD, COMPACT, AND FINE GRADE TOPSOIL TO A SMOOTH AND
- SURFACES OF TURF SOD AREAS, AND 1" BELOW ADJACENT SURFACES OF TURF SEED AREAS. REUSE EXISTING TOPSOIL STOCKPILED ON THE SITE. SUPPLEMENT WITH IMPORTED TOPSOIL WHEN QUANTITIES ARE INSUFFICIENT. VERIFY SUITABILITY AND CONDITION OF TOPSOIL AS A GROWING MEDIUM. PERFORM SOIL TEST/ ANALYSIS AND PROVIDE ADDITIONAL AMENDMENT AS DETERMINED BY SOIL TESTS. TOPSOIL SHALL BE A LOOSE, FRIABLE, SANDY LOAM, CLEAN AND FREE OF TOXIC MATERIALS, NOXIOUS WEEDS, WEED SEEDS, ROCKS, GRASS OR OTHER FOREIGN MATERIAL AND A HAVE A PH OF 5.5 TO 7.0. IF ONSITE TOPSOIL DOES NOT MEET THESE MINIMUM STANDARDS, CONTRACTOR IS RESPONSIBLE TO

UNIFORM GRADE 3" BELOW ADJACENT SURFACES OF PLANTER BED AREAS, 1-1/2" BELOW ADJACENT

- A) PROVIDE APPROVED IMPORTED TOPSOIL, OR B) IMPROVE ON-SITE TOPSOIL WITH METHODS APPROVED BY THE LANDSCAPE ARCHITECT.
- 15. IF IMPORTED TOPSOIL FROM OFF-SITE SOURCES IS REQUIRED, ENSURE IT IS FERTILE, FRIABLE, NATURAL LOAM, SURFACE SOIL, REASONABLY FREE OF SUBSOIL, CLAY LUMPS, BRUSH, WEEDS AND OTHER LITTER, AND FREE OF ROOTS, STUMPS, STONES LARGER THAN 2 INCHES IN ANY DIMENSION, AND OTHER EXTRANEOUS OR TOXIC MATTER HARMFUL TO PLANT GROWTH.
- A) OBTAIN TOPSOIL FROM LOCAL SOURCES OR FROM AREAS HAVING SIMILAR SOIL CHARACTERISTICS TO THOSE FOUND ON THE PROJECT SITE. OBTAIN TOPSOIL ONLY FROM NATURALLY, WELL-DRAINED SITES WHERE TOPSOIL OCCURS AT A DEPTH OF NOT LESS THAN 4 INCHES. B) REPRESENTATIVE SAMPLES SHALL BE TESTED FOR ACIDITY, FERTILITY, TOXICITY, AND GENERAL TEXTURE BY A RECOGNIZED COMMERCIAL OR GOVERNMENT AGENCY AND COPIES OF THE TESTING AGENCY'S FINDINGS AND RECOMMENDATIONS SHALL BE FURNISHED TO THE OWNER'S REPRESENTATIVE BY THE CONTRACTOR. NO TOPSOIL SHALL BE DELIVERED IN A FROZEN OR MUDDY CONDITION. ACIDITY/ALKALINITY RANGE - PH. 5.5 TO 7.6.
- 16. IMMEDIATELY CLEAN UP ANY TOPSOIL OR OTHER DEBRIS ON THE SITE CREATED FROM LANDSCAPE OPERATIONS AND DISPOSE OF PROPERLY OFF SITE.
- 17. TREES SHALL NOT BE PLANTED WITHIN THE 10'-0" CLEAR ZONE OF ALL STORM DRAIN PIPE, STRUCTURES,
- IN THE EVENT OF A DISCREPANCY, NOTIFY THE LANDSCAPE ARCHITECT IMMEDIATELY.

WEED ABATEMENT NOTES:

- - DO NOT WATER FOR AT LEAST SEVEN (7) DAYS. REMOVE EXPOSED WEEDS FROM THE SITE.
 - DAYS. REMOVE WEEDS FROM THE SITE.
- DIRECTED TO PERFORM A THIRD APPLICATION. 7. AT THE TIME OF PLANTING AND HYDROSEEDING, ALL PLANTING AREAS SHALL BE WEED FREE.

IRRIGATION NOTES:

1. ALL LANDSCAPED AREAS SHALL HAVE AN AUTOMATIC UNDERGROUND SPRINKLER SYSTEM WHICH

POP-UP SPRINKLER HEADS SHALL HAVE A MINIMUM RISER HEIGHT OF 4 INCHES AT LAWN AREAS AND 18"

a. PRECISE INDIVIDUAL STATION TIMING b. RUN TIME CAPABILITIES FOR EXTREMES IN PRECIPITATION RATES

e. POWER FAILURE BACKUP FOR ALL PROGRAMMED INDIVIDUAL VALVE WATERING STATIONS WILL BE

DESIGNED AND INSTALLED TO PROVIDE WATER TO RESPECTIVE HYDRO-ZONES.

TRIANGULAR SPACING. SPRINKLER HEADS SHALL BE ADJUSTED TO REDUCE OVER SPRAY ONTO IMPERVIOUS SURFACES

ENTITLEMENT APPLICATION

05/02/25

OVERALL PRELIMINARY LANDSCAPE PLAN

SCALE

1/32" = 1'-0"



/10,138 SF

Block

—SYRINGA LANE -

10,138 SF

10-02-09-4 COMMON OPEN SPACE REQUIREMENTS AND STANDARDS; 10-02-09-5 STREET LANDSCAPE BUFFERS 10-02-09-6BUFFERS BETWEEN DIFFERENT LAND USES; 10-02-09-7 PATHWAY LANDSCAPING STANDARDS TOTAL SITE AREA: 139,360 SF

LANDSCAPE REQUIREMENTS

LANDSCAPE COVERAGE: - SF - 14.9% MINIMUM PLANT SIZES SHALL BE USED: **EVERGREEN TREES:**

ORNAMENTAL TREES: 2" CALIPER SHADE TREES: 2" CALIPER WOODY SHRUBS: 2 GALLON

NUMBER OF TREES PROPOSED: 6 (0 EXISTING/6 PROPOSED)

COMMON OPEN SPACE: PROPOSED AVERAGE LOT SIZE: 7,995.15 SF

REQUIRED % OF OPEN SPACE: 11,149 SF - 8% PROVIDED % OF OPEN SPACE: 27,726.34 SF - 15.16%

1 TREE PER 5,000 S.F. OF AREA, AT LEAST 50% OF REQUIRED TREES SHALL BE CLASS II/III REQUIRED TREES: 6 PROVIDED TREES: 6

9,520 SF

<-SS---- EX-SS---- EX-SS----

_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _

7,056 SF

APPLICABLE CITY OF CALDWELL, IDAHO CODE: 10-02-09-3 LANDSCAPE CRITERIA AND INSTALLATION PRACTICES;

STREET LANDSCAPE BUFFERS: 1 CLASS I TREE PER 25 LIN. FT 1 CLASS II TREE PER 35 LIN. FT.

1 SHRUB PER 4 LIN. FT. OF BUFFER AREA NO MORE THAN 40% OF REQUIRED TREES TO BE OF SAME SPECIES, NO MORE THAN 50% OF REQUIRED TREES SHALL BE CLASS I

SYRINGA LANE (LOCAL): NO LANDSCAPE BUFFER REQUIRED

S. GEORGIA AVENUE (LOCAL): NO LANDSCAPE BUFFER REQUIRED

BUFFERS BETWEEN DIFFERENT LAND USES: NO LANDSCAPE BUFFER REQUIRED

Block 2


PRELIMINARY LANDSCAPE PLAN

CALL 2 BUSINESS DAYS
IN ADVANCE BEFORE
YOU DIG, GRADE, OR
EXCAVATE FOR THE
MARKING OF
UNDERGROUND
MEMBER UTILITIES

PLANTS TO BE INSTALLED

DATE


ENTITLEMENT APPLICATION 05/02/25



PRELIMINARY LANDSCAPE PLAN -AREA ONE

L1.1

1/32" = 1'-0" SCALE



PLANT SCHEDULE

DECIDUOUS TREES

FLOWERING TREES

ORNAMENTAL GRASSES

PERENNIALS

COMMON / BOTANICAL NAME

Acer truncatum x platanoides 'Warrenred' TM

2" Cal. B&B

Pacific Sunset Maple

Bloodgood London Plane Tree

Platanus x acerifolia 'Bloodgood'

Village Green Japanese Zelkova

Zelkova serrata 'Village Green'

Canada Red Chokecherry

Slowmound Mugo Pine

Pinus mugo 'Slowmound'

Flower Carpet Pink Rose

Spiraea japonica 'Neon Flash'

Heavy Metal Switch Grass

Grasspave Porous Grass Paver

1" minus Small Bark Mulch

RTF Sod Rhizomatous Tall Fescue

Karl Foerster Feather Reed Grass

Panicum virgatum 'Heavy Metal' Shenandoah Switch Grass

Panicum virgatum 'Shenandoah'

Leading Lady Amethyst Bee Balm Monarda x 'Leading Lady Amethyst'

COMMON / BOTANICAL NAME

Calamagrostis x acutiflora 'Karl Foerster'


Rosa x 'Noatraum' Neon Flash Spirea

Otto Luyken English Laurel


Prunus laurocerasus 'Otto Luyken'

Prunus virginiana 'Canada Red'

COMMON / BOTANICAL NAME




PRELIMINARY LANDSCAPE PLAN - AREA ONE



REVISION

DATE



TLA 24-19 MORNING STAR DEVELOPMENT

ENTITLEMENT APPLICATION 05/02/25



PRELIMINARY LANDSCAPE PLAN -AREA TWO

L1.2

SCALE

1/32" = 1'-0"

PREVAILING WIND DIRECTION

LEADER!!

RUBBER CINCH TIE

PREVAILING WIND.

SPECIFIED.

FROM TRUNK.

TABLETS

- TOP OF GRASS ROOT MASS 6 MM (1/4") ABOVE TOP OF RING.

- GRASSPAVE 2 ATTACH WITH PEG AND HOLE.

COMPACTED SANDY GRAVEL BASE COURSE.

CONCRETE SAND (CLEAN, SHARP SAND)

— COMPACTED SANDY GRAVEL ROAD BASE - 6" DEPTH.

COMPACTED SUBGRADE, 95% MODIFIED PROCTOR DENSITY

-ROOT MASS TO FILL GRASSPAVE 2.

HYDROGROW MIX BELOW RING SUPPLIED FREE BY MANUFACTURER.

- AFTER INSTALLATION

2"x 2" WOOD STAKE (LENGTH AS

REQUIRED)-DO NOT PENETRATE ROOTBALL
 SEE NOTE 1. SET STAKES PARALLEL TO

REMOVE TREE WRAP TRUNK PROTECTION,

CONSTRUCT 2" EARTH BERM AT EDGE OF ROOTBALL, FILL TREE RING W/ MULCH, AS

- COMMERCIAL SLOW RELEASE FERTILIZER

- BACKFILL WITH APPROVED TOPSOIL AND SOIL AMENDMENTS AS SPECIFIED. BACKFILL IN 6" LIFTS, WATER EACH LAYER, TAMP LIGHTLY AS REQUIRED, BACKFILL

SET ROOTBALL ON NATIVE, UNDISTURBED


- SIDES OF HOLE ROUGH & UNEVEN

SOIL EVEN W/ TOP OF ROOTBALL,

3" THICK MULCH LAYER, KEEP MULCH 3" AWAY

- REMOVE DEAD/DAMAGED BRANCHES AND PRUNE TO INTERNATIONAL SOCIETY OF ARBORICULTURE STANDARDS; IMPROPERLY PRUNED TREES (AS DETERMINED BY THE LANDSCAPE ARCHITECT) SHALL BE REMOVED AND REPLACED. DO NOT REMOVE MAIN

DATE




TLA 24-19 CLIENT MORNING STAR DEVELOPMENT

ENTITLEMENT APPLICATION 05/02/25




PRELIMINARY LANDSCAPE **DETAILS**

SCALE



PLANTER BED CUT EDGE (TYPICAL AT TREES IN TURF AREAS) NOT TO SCALE



- SHRUB SHALL BEAR SAME RELATIONSHIP TO GRADE AS IT DID IN NURSERY. WATER SHRUB TWICE WITHIN FIRST 24 HOURS.
- THIN BRANCHES AND FOLIAGE BY $\frac{1}{3}$. DO NOT CUT LEADERS TO RETAIN NATURAL SHRUB SHAPE.
- FOR CONTAINER GROWN PLANTS THAT ARE ROOTBOUND, SPLIT THE ROOTBALL WITH 3 EQUAL SPACED

SHRUB PLANTING

NOT TO SCALE

NOTES:

WARRANTY PERIOD.

ARCHITECT BEFORE PROCEEDING.

WATER TREE TWICE WITHIN THE FIRST 24 HOURS.

GRASSPAVE SECTION

-ROOT FLARE TO BE AT SOIL LINE

The state of the s

WIDTH | WIDTH | WIDTH \

BIODEGRADABLE BURLAP SHALL BE LEFT ON THE BOTTOM OF THE ROOTBALL

OF BALL OF BALL OF BALL OF BALL SOIL EVEN W/ TOP OF ROOT DO NOT OVER COMPACT!!

REMOVE BURLAP, TWINE, AND WIRE BASKET FROM TOP % OF ROOTBALL. REMOVE ALL NAILS, TIES, AND PLASTIC FROM ROOTBALL. IF SYNTHETIC BURLAP IS UTILIZED TO WRAP THE ROOTBALL, IT SHALL BE COMPLETELY REMOVED. ONLY

AFTER SUBSTANTIAL COMPLETION WHICHEVER IS GREATER. ALL STAKING SHALL BE REMOVED AT THE END OF THE

3. IN THE EVENT OF A QUESTION OR LACK OF CLARITY ON THE DRAWINGS, THE CONTRACTOR IS TO NOTIFY THE LANDSCAPE

LANDSCAPE CONTRACTOR IS TO NOTIFY THE LANDSCAPE ARCHITECT AND OWNER PRIOR TO INSTALLATION OF PLANT

#24-2 OR APPROVED EQUAL). LOCATE ROOT BARRIER AT BACK OF CURB AND EDGE OF SIDEWALK. ALL TREE INSTALLATIONS SHALL CONFORM TO ALL AGENCY APPROVAL REQUIREMENTS, CONTRACTOR SHALL VERIFY PRIOR TO ANY INSTALLATIONS.

SEE ENLARGEMENT

METHOD. SECURE THE TIES TO THE STAKES WITH GALVANIZED NAILS TO PREVENT SLIPPAGE.


DECIDUOUS TREE PLANTING

NOT TO SCALE

NOT TO SCALE

2. THE STAKING OF TREES IS TO BE THE CONTRACTOR'S OPTION: HOWEVER, THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL TREES ARE PLANTED STRAIGHT AND THAT THEY REMAIN STRAIGHT FOR LENGTH OF WARRANTY PERIOD OR 1 YEAR

WRAP RUBBER CINCH TIES AROUND THE TREE TRUNKS AND STAKES USING EITHER THE STANDARD OR FIGURE EIGHT TYING IN THE EVENT HARDPAN SOILS PREVENT TREE PLANTING AS DETAILED, NOTIFY THE LANDSCAPE ARCHITECT IMMEDIATELY. FOR TREES LOCATED WITHIN ROADSIDE PLANTERS LESS THAN 8'-0" IN WIDTH, PROVIDE TREE ROOT BARRIER (DEEPROOT



1/32" = 1'-0"

DATE

ENTITLEMENT APPLICATION 05/02/25



OPEN SPACE EXHIBIT

L1.6

SCALE 1/32" = 1'-0"































Street Name Request Form		Ç.											
Project Name: Patriots La Project Location: South of S. G. Submittal Number:	nd	ñ٢	NA.										Approved:
Project Location: South of C. G.	co	ra	8	n	- Ar	d	8,	(Y)	<u>∩</u> α	e 1	m		Resubmission Required:
Submittal Number:			Da	ite:					6			10	<i>fersection</i>
S							F	OR	t S1	ΓAF	FF	REV	IEW
	Τ	Str	eet	Naı	me			Str	eet	Sut	ffix		
Requested Street Name	Ap	prov	/ed	D	Denied			Approved			enie	ed	Notes
Obyhee of Patriot Ridge Avc	T												
Outshee 87													
Patrict Ridge Ave.													
												-Levilledinian	
W SYSTEM A SERVICE AND A SERVI				,									
												-	
497													
													-2
•													
												,	
													-
													2
												•	
													===403, 3009, 320
													11 (172)

Property Owner Acknowledgement

1, Tinothy W Davis, Patriot Lyulia W., the record owner for real property addressed as 2422 5yringa Lang, Coldwell to, am aware of, in agreement with, and give
as 2472 5yringa Lary, Coldwell 40, am aware of, in agreement with, and give
my permission to Andrew Wheeler Architect to submit the
accompanying application(s) pertaining the that property.
 I agree to indemnify, defend and hold the City of Caldwell and its employees harmless from any claim or liability resulting from any dispute as to the statement(s) contained herein or as to the ownership of the property which is the subject of the application. I hereby grant permission to City of Caldwell staff to enter the subject property for the purpose of
site inspection(s) related to processing said application(s).
D. Oth
Dated this Dated this day of february 2025
(Cinnahura)
(Signature)
(Signature)
CERTIFICATE OF VERIFICATION
CERTIFICATE OF VERIFICATION STATE OF IDAHO Ada State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO State Of IDAHO Ada State Of IDAHO State Of IDAHO Ada State Of IDAHO Ada State Of IDAHO State Of IDAHO Ada State Of IDAHO State Of IDAHO
CERTIFICATE OF VERIFICATION STATE OF IDAHO AIK)

RECORDED

08/15/2024 03:16 PM

RICK HOGABOAM CANYON COUNTY RECORDER

Pgs=5 JWINSLOW

\$15.00

TYPE: DEED

VENTURE TITLE & ESCROW COMPANY ELECTRONICALLY RECORDED



Warranty Deed

For value received,

Jerry E. Vavold, an unmarried person

the grantor, does hereby grant, bargain, sell, and convey unto

Patriot Landing LLC, an Idaho limited liability company

whose current address is 22493 Duff Lane, Middleton, ID 83644

the grantee, the following described premises, in Canyon County, Idaho, to wit:

See Attached Exhibit A

To have and to hold the said premises, with their appurtenances unto the said Grantee, its heirs and assigns forever. And the said Grantor does hereby covenant to and with the said Grantee, that Grantor is the owner in fee simple of said premises; that they are free from all encumbrances except those to which this conveyance is expressly made subject and those made, suffered or done by the Grantee; and subject to all existing patent reservations, easements, right(s) of way, protective covenants, zoning ordinances, and applicable building codes, laws and regulations, general taxes and assessments, including irrigation and utility assessments (if any) for the current year, which are not due and payable, and that Grantor will warrant and defend the same from all lawful claims whatsoever. Whenever the context so requires, the singular number includes the plural.

Remainder of page intentionally left blank.

Dated: August 6, 2024

Jerry E. Vavold

State of Idaho,

County of Canyon, ss:

This record was signed or acknowledged before me on this 14th day of August, 2024, by Jerry E. Vavold.

Notary Public

Residing In:

My Commission Expires:

(seal)

NICOLE YORK COMMISSION #20170592 NOTARY PUBLIC STATE OF IDAHO

MY COMMISSION EXPIRES 09/25/2029

Exhibit A

Legal Description of the Premises

Parcel I:

A parcel of land being a portion of Tract 12 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, lying in the Southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, and more particularly described as follows:

Beginning at the Northeast corner of said Tract 12, a point marked by a 5/8" iron pin; thence along the North line of said Tract 12

North 89°54'12" West, a distance of 133 feet to a point marked by a 5/8" iron pin; thence along a line 133 feet West of and parallel with the East line of said Tract 12

South 00°07'29" West, a distance of 170 feet to a point marked by a 5/8" iron pin; thence along a line 170 feet South of and parallel to the North line of said Tract 12

South 89°54'12" East, a distance of 133 feet to a point on the East line of said Tract 12 marked by a 5/8" iron pin; thence along the East line of said Tract 12

North 00°07'29" East, a distance of 170 feet to the Point of Beginning.

Together with a 4' wide strip of land along the Easterly boundary of said Tract 12, vacated by the City of Caldwell, as disclosed by Ordinance No. 2452, recorded January 9, 2003 as Instrument No. 200301400, and re-recorded January 19, 2021 as Instrument No. 2021-003881, records of Canyon County, Idaho.

Parcel II:

A parcel of land being a portion of Tract 12 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, lying in the Southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, and more particularly described as follows:

Commencing at an iron pin marking the Northeast corner of the said Tract 12; thence along the Easterly boundary of the said Tract 12

South 00°07'29" West, 170.00 feet to an iron pin, also said point the Real Point of Beginning; thence continuing

South 00°07'29" West, 359.67 feet to an iron pin on the Northeasterly right of way line of Interstate I-84; thence along the said Northeasterly right of way line

North 60°57'06" West, 151.95 feet to an iron pin; thence leaving the said Northeasterly right of way line along a line 133.00 feet Westerly of and parallel with the said Easterly boundary of Tract 12

North 00°07'29" East, 286.11 feet to an iron pin; thence along a line 170.00 feet Southerly of and parallel with the Northerly boundary of the said Tract 12

South 89°54'12" East, 133.00 feet to the Point of Beginning.

File Number: V2413145

Together with a 4' wide strip of land along the Easterly boundary of said Tract 12, vacated by the City of Caldwell, as disclosed by Ordinance No. 2452, recorded January 9, 2003 as Instrument No. 200301400, and re-recorded January 19, 2021 as Instrument No. 2021-003881, records of Canyon County, Idaho.

Parcel III:

A parcel of land being a portion of Tract 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, lying in the Southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, and more particularly described as follows:

Commencing at a point marking the Northwest corner of the said Tract 13; thence along the Westerly boundary of the said Tract 13

South 00°07'29" West, 302.01 feet to an iron pin, said point being the Real Point of Beginning; thence leaving the said Westerly boundary

South 89°55'48" East, 301.99 feet to an iron pin; thence

South 00°05'47" West, 301.87 feet to an iron pin; thence along a line 30.00 feet Northerly of and parallel with the Southerly boundary of the said Tract 13

North 89°57'25" West, 227.83 feet to an iron pin on the Northeasterly right of way line of Interstate I-84; thence along the said Northeasterly right of way line

North 60°57'06" West, 84.90 feet to an iron pin on the said Westerly boundary of Tract 13; thence along the said Westerly boundary

North 00°07'29" East, 260.84 feet to the Point of Beginning.

Excepting therefrom, a portion of Tract 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, also designated as a portion of Parcel 3 of Record of Survey recorded December 15, 1994 as Instrument No. 9437239, records of Canyon County, Idaho, and being a portion of the Southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, and more particularly described as follows:

Commencing at a brass marker located at Station 1514+80.00 on the Northeasterly right of way line of Interstate I-84; thence

North 60°57'06" West, a distance of 1418.44 feet to a point on the South boundary of said Parcel 3, and the True Point of Beginning; thence continuing along said right of way line North 60°57'06" West, a distance of 84.90 feet to a point on the Westerly right of way line of South Georgia Avenue; thence along said right of way line of South Georgia Avenue North 00°07'29" East, a distance of 75.78 feet to a point of curvature; thence along said curve to the left, a distance of 21.32 feet, said curve having a radius of 20.00 feet, a central angle of 61°04'35", a long chord bearing South 30°24'48" East, a distance of 20.32 feet to a point of tangency; thence

South 60°57'06" East, a distance of 199.89 feet to a point of curvature; thence along said curve to the left, a distance of 10.12 feet, said curve having a radius of 20.00 feet, a central angle of

File Number: V2413145

29°00'19", and a long chord bearing South 75°27'15" East, a distance of 10.02 feet to a point on the South boundary of said Parcel 3; thence along said South boundary North 89°57'25" West, a distance of 120.67 feet to the Point of Beginning.

Parcel IV:

The South half of the West half of Tract 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, lying in the North half of the Southwest quarter and the Northwest quarter of the Southeast quarter of Section 23, Township 4 North, Range 3 West of the Boise Meridian, Canyon County, Idaho.

Excepting therefrom, a triangular parcel of land being on the Northeasterly side of right of way survey line, and lying over and across the Southwest corner of Tract 13 of said Hillcrest Subdivision, described as follows:

Beginning at the Southwest corner of Tract 13 of said Hillcrest Subdivision; thence North along the West line of said Tract 13, a distance of 30.0 feet, more or less, to a point; thence South 61°36" East, along a line 110.0 feet distant Northeasterly from and parallel to said right of way survey line, a distance of 62.0 feet, more or less, to a point on the South line of said Tract 13; thence

West along the South line of said Tract 13, a distance of 54.0 feet, more or less, to the Point of Beginning.

Also excepting therefrom, a parcel of land being a portion of Tract 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page(s) 10, records of Canyon County, Idaho, lying in the Southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Caldwell, Canyon County, Idaho, and more particularly described as follows:

Commencing at a point marking the Northwest corner of the said Tract 13; thence along the Westerly boundary of the said Tract 13

South 00°07'29" West, 302.01 feet to an iron pin, said point being the Real Point of Beginning; thence leaving the said Westerly boundary

South 89°55'48" East, 301.99 feet to an iron pin; thence

South $00^{\circ}05'47''$ West, 301.87 feet to an iron pin; thence along a line 30.0 feet Northerly of and parallel with the Southerly boundary of the said Tract 13

North 89°57'25" West, 227.83 feet to an iron pin on the Northeasterly right of way line of Interstate I-84; thence along the said Northeasterly right of way line

North 60°57'06" West, 84.90 feet to an iron pin on the said Westerly boundary of Tract 13; thence along the said Westerly boundary

North 00°07'29" East, 260.84 feet to the Point of Beginning.



CENTURION ENGINEERS. INC.

Consulting Engineers, Land Surveyors and, Planners 2323 S. Vista Ave, Suite 206 Boise, ID 83705 Telephone 208.343.3381 | www.centengr.com

Patriot Landing Subdivision Rezone Description R-1 to R-2

18 September 2025

A parcel of land being a portion of Tracts 12 and 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page 10, records of Canyon County, Idaho and adjoining right-of-way. Situate in the southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, being more particularly described as follows:

Commencing at the west quarter corner of said Section 23; thence S89°53'24"E, 1,325.14 feet along the northerly boundary of the northwest quarter of the southwest quarter of said Section 23 to the northeast corner of northwest quarter of the southwest quarter of said Section 23, which bears N89°52'25"W, 1,326.16 feet from the center quarter of said Section 23; thence S00°05'32"W, 663.72 feet along the easterly boundary of the northwest quarter of the southwest quarter of said Section 23 to the centerline of Syringa Lane; thence N89°55'43"W, 163.00 feet along the centerline of Syringa Lane; thence S00°05'58"W, 30.00 feet to the southerly right-of-way of Syringa Lane; thence continuing S00°05'58"W, 77.28 feet to the *Point of Beginning:*

Thence S89°55'43"E, 165.00 feet along a line parallel to the southerly right-of-way of Syringa Lane to the centerline of Patriot Ridge Avenue;

Thence S00°05'58"W, 224.74 feet along the centerline of Patriot Ridge Avenue;

Thence S89°57'16"E, 344.99 feet;

Thence S00°04'16"W, 331.86 feet to the centerline of Owyhee Street:

Thence N89°58'56"W, 188.68 feet along the centerline of Owyhee Street to the northeasterly right-of-way of I-84;


Thence N60°58'37"W, 367.29 feet along the northeasterly right-of-way of I-84;

Thence N00°05'58"E, 378.83 feet to the *Point of Beginning*.

Comprising 4.08 acres, more or less.



Patriot Landing Rezone Exhibit






Consulting Engineers, Land Surveyors, Planners 2323 S. Vista Ave. Suite 206 | Boise, ID 83705 208.343.3381 | www.centengr.com



SCALE: 1"=80"

Patriot Landing Vicinity Map





CENTURION ENGINEERS, INC.

Consulting Engineers, Land Surveyors, Planners 2323 S. Vista Ave. Suite 206 | Boise, ID 83705 208.343.3381 | www.centengr.com



SCALE: 1"=80"



CENTURION ENGINEERS. INC.

Consulting Engineers, Land Surveyors and, Planners 2323 S. Vista Ave, Suite 206 Boise, ID 83705 Telephone 208.343.3381 | www.centengr.com

Patriot Landing Subdivision Subdivision Boundary Description

18 September 2025

A parcel of land being a portion of Tract 12 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page 10, records of Canyon County, Idaho and adjoining vacated right-of-way. Situate in the southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, being more particularly described as follows:

Commencing at the west quarter corner of said Section 23; thence S89°53'24"E, 1,325.14 feet along the northerly boundary of the northwest quarter of the southwest quarter of said Section 23 to the northeast corner of northwest quarter of the southwest quarter of said Section 23, which bears N89°52'25"W, 1,326.16 feet from the center quarter of said Section 23; thence S00°05'32"W, 663.72 feet along the easterly boundary of the northwest quarter of the southwest quarter of said Section 23 to the centerline of Syringa Lane to Point "A"; thence N89°55'43"W, 163.00 feet along the centerline of Syringa Lane; thence S00°05'58"W, 30.00 feet to the southerly right-of-way of Syringa Lane; thence continuing S00°05'58"W, 77.28 feet to the **Point of Beginning:**

Thence S89°55'43"E, 137.00 feet along a line parallel to the southerly right-of-way of Syringa Lane to the westerly right-of-way of Patriot Ridge Avenue being 4.00 feet easterly of the easterly boundary of said Tract 12:

Thence S00°05'58"W, 454.60 feet along the westerly right-of-way Patriot Ridge Avenue and along a line 4.00 feet easterly of and parallel with the easterly boundary of said Tract 12 to the northeasterly right-of-way of Interstate I-84;

Thence N60°58'37"W, 156.52 feet along the northeasterly right-of-way of Interstate I-84;

Thence N00°05'58"E, 378.83 feet to the *Point of Beginning*.

AND the following described parcel of land:

A parcel of land being a portion of Tract 13 of Hillcrest Subdivision, according to the official plat thereof, filed in Book 3 of Plats at Page 10, records of Canyon County, Idaho. Situate in the southwest quarter of Section 23, Township 4 North, Range 3 West, Boise Meridian, Canyon County, Idaho, being more particularly described as follows:

Commencing at Point "A" as described above; thence S00°05'58"W, 332.02 feet; thence S89°57'16"E, 30.00 feet to the easterly right-of-way of Patriot Ridge Avenue and to the *Point of Beginning:*

Thence continuing S89°57'16"E, 316.99 feet;

Thence S00°04'16"W, 301.86 feet to the northerly right-of-way of Owyhee Street;

Thence N89°58'56"W, 122.15 feet along the northerly right-of-way of Owyhee Street to a Point of Curvature;

Thence along the northerly right-of-way of Owyhee Street, 10.12 feet along a tangent curve deflecting to the right, with a radius of 20.00 feet, a central angle of 29°00'19", a long chord of 10.02 feet and a chord bearing of N75°28'47"W to a Point of Tangency;

Thence N60°58'37"W, 199.89 feet along the northeasterly right-of-way of Owyhee Street to a Point of Curvature;

Thence along the northeasterly right-of-way of Owyhee Street, 21.32 feet along a tangent curve deflecting to the right, with a radius of 20.00 feet, a central angle of 61°04'35", a long chord of 20.32 feet and a chord bearing of N30°26'19"W to a Point of Tangency;

Thence N00°05'58"E, 185.06 feet along the easterly right-of-way of Patriot Ridge Avenue to the *Point of Beginning*.

Subject to easements of record or apparent.

Comprising a total land area of 3.28 acres, more or less.